

3-8

To: 070649
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-025-21,022-0000
100' S of
C W/2 W/2, SEC. 12, T 34 S, R 22 W/EX
2540 feet from S section line
4620 feet from E section line

TECHNICIAN'S PLUGGING REPORT
Operator License # 5003
Operator: McCoy Petroleum Corporation
Name & Address: 110 South Main, Suite 500
Wichita, KS 67202

Lease Name Randall "A" Well # 1-12
County Clark 181.03
Well Total Depth 5570 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 804

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D&A X

Other well as hereinafter indicated _____

Plugging Contractor Allen Drilling Inc. License Number 5418

Address P.O. Box 1389, Great Bend, KS 67530

Company to plug at: Hour: 6:30 p.m. Day: 8 Month: 3 Year: 19 89

Plugging proposal received from Craig Christopher

(company name) Allen Drilling Inc. (phone) 316-793-3582

were: to fill hole with heavy mud and spot cement through drill pipe Anhydrite 866-76'

- 1st plug at 850' with 50 sx cement,
- 2nd plug at 400' with 40 sx cement,
- 3rd plug at 40' with 10 sx cement,
- 4th plug to circulate rathole with 15 sx cement.

Plugging Proposal Received by Dan Goodrow (TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part _____ None X

Operations Completed: Hour: 8:30 p.m. Day: 8 Month: 3 Year: 19 89

ACTUAL PLUGGING REPORT 1st plug at 850' with 50 sx cement, RECEIVED STATE CORPORATION COMMISSION

2nd plug at 400' with 40 sx cement,

3rd plug at 40' with 10 sx cement, MAR 13 1989 3-13-89

4th plug to circulate rathole with 15 sx cement.

CONSERVATION DIVISION
Wichita, Kansas

Remarks: Used 60/40 Pozmix 6% gel by Halliburton.
(if additional description is necessary, use BACK of this form.)

INVOICED (did not observe this plugging.)

DATE 3-14-89

Signed Dan Goodrow (TECHNICIAN)

INV. NO. 24088 3-8