

2-3-88

To: 1 061060  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15- 025-20,205-A -0001  
C SE NE, SEC. 9, T 34 S, R 22 W/8  
3300 feet from S section line  
660 feet from E section line

TECHNICIAN'S PLUGGING REPORT  
Operator License # 5364  
Operator: Beren Corporation  
Name & Address: 970 Fourth Financial Center  
Wichita, KS 67202

Lease Name Blackhall Well # 1  
County Clark 182.55  
Well Total Depth 5617 feet  
Conductor Pipe: Size \_\_\_\_\_ feet  
Surface Casing: Size 8 5/8 feet 707

Abandoned Oil Well  Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A \_\_\_\_\_

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Kelso Casing Pulling License Number 6050  
Address Box 347, Chase, KS 67524

Company to plug at: Hour: 10 a.m. Day: 3 Month: 2 Year: 19 88

Plugging proposal received from Vernon Duntz

(company name) Kelso Casing Pulling (phone) 316-938-2457

were: 4 1/2" at 5628' PBD 5574' Perfs at 5421-27, 5480-90' Elevation 1877' GL

1st plug sand back to 5375' and dump 4 sx cement on top of sand through bailer,  
2nd plug pump 4 sx hulls, 10 sx gel and 150 sx Thrifty Mix.

Plugging Proposal Received by Richard Lacey (TECHNICIAN)

Plugging Operations attended by Agent?: All  Part \_\_\_\_\_ None \_\_\_\_\_

Operations Completed: Hour: 11 a.m. Day: 3 Month: 2 Year: 19 88

ACTUAL PLUGGING REPORT 1st plug sanded back to 5375' and dumped 4 sx cement on top of sand through bailer,

2nd plug pumped 4 sx hulls, 10 sx gel and 150 sx Thrifty Mix.

RECEIVED  
STATE CORPORATION COMMISSION  
2-8-88  
FEB 08 1988

Maximum pressure 800 psi and shut in 400 psi.

CONSERVATION DIVISION  
Wichita, Kansas

Remarks: Used Thrifty Mix by B.J. Titan. Recovered 4300' of 4 1/2" casing.  
(If additional description is necessary, use BACK of this form.)

INVOICED

DATE 2-10-88  
INV. NO. 19800

Signed Paula A. Luthi (TECHNICIAN)