

To: **1 120448**
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

TECHNICIAN'S PLUGGING REPORT

Operator License # 6574

Operator: Bird Energy, Inc.

Name & Address Box 1612

Dodge City, KS 67801

Abandoned Oil Well ☐ Gas Well ☐ Input Well ☐ SWD Well ☐ D&A ☒

Other well as hereinafter indicated

Plugging Contractor Eagle Drilling, Inc. License Number 5380

Address P.O. Box 12383, Wichita, KS 67277-2383

Company to plug at: Hour: 4:45 a.m. Day: 4 Month: 7 Year: 19 90

Plugging proposal received from Butch Steinert

(company name) Eagle Drilling, Inc. (phone) 316-945-9935

work: to fill hole with heavy mud and spot cement through drill pipe Anhydrite 910-36'

1st plug at 950' with 50 sx cement,

2nd plug at 660' with 50 sx cement,

3rd plug at 40' with 10 sx cement, 4th plug to circulate rathole with 15 sx cement,

5th plug to circulate mousehole with 10 sx cement.

Plugging Proposal Received by Duane Rankin
(TECHNICIAN)

Plugging Operations attended by Agent?: All ☐ Part ☐ None ☒

Operations Completed: Hour: 6:45 a.m. Day: 4 Month: 7 Year: 19 90

ACTUAL PLUGGING REPORT 1st plug at 950' with 50 sx cement,

2nd plug at 660' with 50 sx cement,

3rd plug at 40' with 10 sx cement,

4th plug to circulate rathole with 15 sx cement,

5th plug to circulate mousehole with 10 sx cement.

Remarks: Used 60/40 Pozmix 6% gel by Allied.

(If additional description is necessary, use BACK of this form.)

INVOICED (I did not) observe this plugging.

DATE 7-17-90

INV. NO. 28586

7-4

Signed Duane Rankin
(TECHNICIAN)