

To: 1 030663
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 025-20,941 - 0000

SE SE SW, SEC. 5, T 34 S, R 22 ^{XX}

330 feet from S section line

2994 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 4611

Lease Name Huber Well # 1-5

Operator: Celeron Oil & Gas Company
Name & Address: 5445 DTC Parkway, Suite 1100
Englewood, CO 80111

County Clark 185.25

Well Total Depth 5700 Mississippi feet

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 710

Abandoned Oil Well Gas Well Input Well SWD Well D&A X

Other well as hereinafter indicated

Plugging Contractor Eagle Drilling, Inc. License Number 5380

Address P. O. Box 8609, Wichita, KS 67208

Company to plug at: Hour: 8:00 pm Day: 12 Month: February Year: 19 86

Plugging proposal received from Butch Steinert

(company name) Eagle (phone) 316-682-5513

were: to fill hole with heavy mud and spot cement through drill pipe Elevation 1927 Anhydrite 1200

1st plug at the base of the Anhydrite with 50 sx cement

2nd plug 30' below the base of the surface pipe with 40 sx cement
solid bridge

3rd plug hulls - plug at 40' -- cement to surface with 10 sx cement

5th plug to circulate rat hole with 10 sx cement

6th plug to circulate mouse hole with 10 sx cement

Plugging Proposal Received by Steve Durrant

(TECHNICIAN)

X

Plugging Operations attended by Agent?: All Part None

Operations Completed: Hour: 10:30 pm Day: 12 Month: February Year: 19 86

ACTUAL PLUGGING REPORT 1st plug at 1200' with 50 sx cement, 2nd plug at 740' with 40 sx cement, 3rd & 4th plugs - solid bridge - hulls - plug at 40' -- cement to surface with 10 sx cement, 5th plug to circulate rat hole with 10 sx cement, 6th plug to circulate mouse hole with 10 sx cement.

STATE CORPORATION COMMISSION

MAR 4 1986

Remarks: Used 60/40 Pozmix 6% gel by Halliburton.

(If additional description is necessary, use BACK of this form, Kansas)

INVOICED did not observe this plugging.

Signed Steve Durrant (TECHNICIAN)

DATE MAR 04 1986
INV. NO. 12859