

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-025-00053-00-00
Spot: N2S2 Sec/Twnshp/Rge: 1-34S-22W
2110 feet from S Section Line, 2640 feet from W Section Line
Lease/Unit Name: RANDELL Well Number: 1
County: CLARK Total Vertical Depth: 5555 feet

Operator License No.: 31925
Op Name: QUALITY WELL SERVICE, INC.
Address: 401 WEST MAIN
LYONS, KS 67554

Production Casing Size: 4.5 feet: 5555
Surface Casing Size: 8.625 feet: 633

18054

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 09/05/2003 9:00 AM
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.
Proposal Rcvd. from: JOE MAAS Company: QUALITY WELL SERVICE, INC. Phone: (620) 278-2026

Proposed Plugging Method: SAND TO 5300' & 4 SX CMT. PLUG AT 900' WITH 50 SX CMT. PLUG AT 660' WITH 50 SX CMT. PLUG AT 40' WITH 10 SX CMT.

Plugging Proposal Received By: STEVE MIDDLETON WitnessType: Plugging Operations 100% Witnessed (Complete)
Date/Time Plugging Completed: 09/05/2003 10:00 AM KCC Agent: STEVE MIDDLETON

Actual Plugging Report:
PERFS AT 4500'-5395'. SAND TO 4450' WITH 4 SX CMT. 1ST PLUG PULL CASING TO 950' & SPOT 10 SX GEL & 50 SX CMT. 2ND PLUG PULL TO 660' & SPOT 50 SX CMT. 3RD PLUG PULL TO 40' & SPOT 10 SX CMT. STAYED FULL.

RECEIVED
SEP 19 2003
KCC WICHITA

Remarks: USED 60/40 POZMIX 6% GEL BY ALLIED. RECOVERED 2950' OF 4 1/2" CASING.
Plugged through: CSG

District: 01

RECEIVED
SEP 17 2003
KCC Dodge City

Signed _____
(TECHNICIAN)

INVOICED
DATE 9-19-03
INV. NO. 2004060527

Form CP-2/3