

1050374

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15- 025-20,853-0000

C SE NE, SEC. 16, T 34 S, R 22 W/E  
3300 feet from ~~N~~ SE Corner of ~~N~~ section line  
660 feet from ~~W~~ SE Corner of ~~W~~ section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5652 5313

Lease Name Rankin Well # 1-16

Operator: Mustang Drilling & F & M Oil Co.  
Name & Address: 200 W. Douglas, Suite 800  
Wichita, KS 67202

County Clark

Well Total Depth 5558 180.64 feet

Conductor Pipe: Size \_\_\_\_\_ feet

Surface Casing: Size 8 5/8 feet 630

Abandoned Oil Well \_\_\_\_\_ Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Union Drilling Company License Number 5103

Address 200 Classen Center, South Building, Oklahoma City, OK 73106

Company to plug at: Hour: 5:00 am Day: 7 Month: November Year: 19 84

Plugging proposal received from Brown

(company name) Union Drilling Co. (phone) 405-528-7601

were: to fill hole with heavy mud and spot cement through drill pipe

1st plug at 1410' with 50 sx cement

2nd plug at 660' with 50 sx cement

3rd plug hulls - plug at 40' -- cement to surface with 10 sx cement

5th plug to circulate rat hole with 10 sx cement

6th plug to circulate mouse hole with 10 sx cement

Plugging Proposal Received by Richard N. Lacy  
(TECHNICIAN)

Plugging Operations attended by Agent?: All \_\_\_\_\_ Part \_\_\_\_\_ None

Operations Completed: Hour: 7:00 am Day: 7 Month: November Year: 1984

ACTUAL PLUGGING REPORT 1st plug at 1410' with 50 sx cement, 2nd plug at 660' with 50  
sx cement, 3rd & 4th plugs - solid bridge - hulls - plug at 40' -- cement to surface with 10  
sx cement, 5th plug to circulate rat hole with 10 sx cement, 6th plug to circulate  
mouse hole with 10 sx cement.

Remarks: Used 60/40 Pozmix 2% gel 3% cc by Sun.

(If additional description is necessary, use BACK of this form.)

INVOICED

(do not) observe this plugging.

DATE 11-19-84

Signed Richard N. Lacy  
(TECHNICIAN)

INV. NO. 4802

DEC 07 1984