

1 080563

23R

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15-025-20,830-~~0000~~  
SW NE NE, SEC. 15, T 34 S, R 22 W/E

TECHNICIAN'S PLUGGING REPORT

Operator License # 5398

4040 feet from S section line  
1230 feet from E section line

Operator: Arco Oil & Gas Company  
Name & Address: 1112 11th Street  
Woodward, OK 73801

Lease Name Shurtleff Well # 2-15X  
County Clark 182.00  
Well Total Depth 5600 feet  
Conductor Pipe: Size \_\_\_\_\_ feet  
Surface Casing: Size 8 5/8 feet 701

Abandoned Oil Well  Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A \_\_\_\_\_

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Wilson Casing Pulling, Inc. License Number 3158

Address P.O. Box 963, Woodward, OK 73801

Company to plug at: Hour: 11 a.m. Day: 7 Month: 11 Year: 19 86

Plugging proposal received from Sid Wilson

(company name) Wilson Casing Pulling (phone) \_\_\_\_\_

were: 5 1/2" at 5600' Perfs at 5430-34' Elevation 1849' GL

1st plug retainer at 5400' and dump 10 sx cement on top with tubing,

2nd plug-to plug through casing-spot bottom plug, circulate casing with mud - shoot off and pull to 930', spot 40 sx (displace with mud) cement - pull to 730', spot 40 sx cement

(displace with mud) - pull to 40'- 10 sx cement.

Plugging Proposal Received by Don Ubel  
(TECHNICIAN)

Plugging Operations attended by Agent?: All  Part \_\_\_\_\_ None \_\_\_\_\_

Operations Completed: Hour: 3 p.m. Day: 7 Month: 11 Year: 19 86

ACTUAL PLUGGING REPORT 1st plug sanded back to 5400' and dumped 10 sx cement through tubing,

2nd plug pumped 20 lbs. 9:5 mud and 40 sx cement at 930', displaced with 18 lbs., pumped

40 sx cement at 730', pumped 10 sx cement at 40'.

11-12-86  
NOV 12 1986

Remarks: Recovered 3268' of 5 1/2" casing. Used Class H cement by Wilson.  
(If additional description is necessary, use BACK of this form.)

INVOICED (If additional description is necessary, use BACK of this form.) observe this plugging.

DATE 11-12-86

Signed J. A. [Signature]  
(TECHNICIAN)

INV. NO. 15397  
11-7