

1 060604

API NUMBER 15- 129-20,761-0000 *R*

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

SW NE NW, SEC. 19, T 33 S, R 42 *(W/EX)*

4514 feet from S section line

3406 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5447

Lease Name Williams "D" Well # 3

Operator: Cities Service Oil & Gas Corp.

County Morton 163.15

Name & Address 3545 NW 58th Street

Well Total Depth 5020 (Chester) feet

Oklahoma City, OK 73112

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8" feet 1356

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D&A *X*

Other well as hereinafter indicated _____

Plugging Contractor Zenith Drilling Corp. License Number 5141

Address 505 Fourth Financial Center, Wichita, KS 67202

Company to plug at: Hour: 9:00 am Day: 3 Month: July Year: 19 85

Plugging proposal received from Bob Gilliam

(company name) Cities Service (phone) 405-949-4400
Elevation 3556.7

were: to fill hole with heavy mud and spot cement through drill pipe Anhydrite 1346

1st plug at 5020' with 35 sx cement 2nd plug at 4700' with 50 sx cement

3rd plug at 3053' with 75 sx cement 4th plug at 1458' with 50 sx cement

5th plug at 750' with 35 sx cement 6th plug hulls - plug at 40' -- cement to surface with 10 sx cement

8th plug to circulate rat hole with 15 sx cement

9th plug to circulate mouse hole with 10 sx cement
Plugging Proposal Received by Paul A. Luthi
(TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part _____ None *x*

Operations Completed: Hour: 11:00 am Day: 3 Month: July Year: 19 85

ACTUAL PLUGGING REPORT 1st plug at 5020' with 35 sx cement, 2nd plug at 4700' with 50

sx cement, 3rd plug at 3053' with 75 sx cement, 4th plug at 1458' with 50 sx cement,

5th plug at 750' with 35 sx cement, 6th & 7th plug - solid bridge - hulls - plug at 40'

cement to surface with 10 sx cement, 8th plug to circulate rat hole with 15 sx cement,

9th plug to circulate mouse hole with 10 sx cement.

(1st plug - used 60/40 Pozmix all others -

Remarks: Used Class H cement by Dowell)

(If additional description is necessary, use BACK of this form.)

INVOICED

DATE 7-17-85

INV. NO. 8995

7-3

RECEIVED
STATE CORPORATION COMMISSION

7-9-85

Signed Paul A. Luthi
(TECHNICIAN)

CARD MUST BE TYPED

State of Kansas
NOTICE OF INTENTION TO DRILL
(see rules on reverse side)

Amended to show correction in Range location. * *corrected*

CARD MUST BE SIGNED

62085

Starting Date: June 28, 1985
month day year

API Number 15- 129-20761

OPERATOR: License # 5447
Name Cities Service Oil and Gas Corp.
Address 3545 NW 58th Street
City/State/Zip Oklahoma City, OK 73112
Contact Person Raymond Hui
Phone (405) 949-4400

* SW NE NW Sec 19 Twp 33 S Rge 42 E
(location) 766' FNL; 1874' FWL East West

..4514 Ft North from Southeast Corner of Section
..3406 Ft West from Southeast Corner of Section
(Note: Locate well on Section Plat on reverse side)

Nearest lease or unit boundary line 766 feet.
County Morton

Lease Name Williams "D" Well# 3

Domestic well within 330 feet: yes no
Municipal well within one mile: yes no

Depth to Bottom of fresh water Est. 625 feet

Lowest usable water formation Est. Permian

Depth to Bottom of usable water Est. 750 feet

Surface pipe by Alternate: 1 2

Surface pipe to be set 1350 feet

Conductor pipe if any required feet

Ground surface elevation Est. 3555 feet MSI

This Authorization Expires 12-14-85

Approved By 6-14-85

CONTRACTOR: License # 5141
Name *Smith Drilling Not yet known Corp.*

City/State *SOS 4th Financial Center*
Well Drilled For: *Wichita* Well Class: 67202 Type Equipment:

X Oil Swd X Infield Mud Rotary
Gas Inj Pool Ext. Air Rotary
 OWWO Expl Wildcat Cable

If OWWO: old well info as follows:

Operator

Well Name

Comp Date Old Total Depth

Projected Total Depth 5000' feet

Projected Formation at TD Chester

Expected Producing Formations Morrow

I certify that we will comply with K.S.A. 55-101, at seq., plus eventually plugging hole to K.C.C. specifications. *was 19-33-43v*

Date 6-19-85 Signature of Operator or Agent *Raymond Hui* Title Supervisor, Oil & Gas Systems

moved - see other sheet

RECEIVED
STATE CORPORATION COMMISSION
JUN 19 09 1985
CONSERVATION DIVISION
Wichita, Kansas