

State of Kansas



# State Corporation Commission

## CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market  
WICHITA, KANSAS 67202

### VERBAL PERMIT FORM (To Be Filed By Plugging Agent)

RECEIVED  
STATE CORPORATION COMMISSION  
DEC 23 1971  
CONSERVATION DIVISION  
Wichita, Kansas

J. Lewis Brock  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

Dear Sir:

Mr. Gatlin of Anadarko has this

date requested permission to plug the following described well:

Mr. Gatlin guarantees payment of the plugging fee.

Operator's full Name: Anadarko Production Co.

Complete Address: Box 351, Liberal, Kansas

Lease Name: Linscott "B" Well No. 3

Location: App C S/2 SW Sec. 32 Twp. 34 Rge. 43 (W)

County: Morton Total Depth 4590' Oil Well X

Gas Well      Input Well      SWD Well      D & A      X Lost Hole     

Mr. Gatlin was instructed to plug the well as follows:

8 5/8" to 1239' circulated w/ cement. 5 1/2" to 4360' cemented.


Top perforations App/ 4200' Plug bottom w/ 25 sacks cement .

Top of cement 3616' Mud 3616' to 1000'

Spot 35 sacks cement 1000' to 900' Mud 900' to 45'

Plug, Halls & 15 sacks cement 45' to 0'.

Very truly yours,

  
Conservation Division Agent