

State of Kansas



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION
DEC 21 1971
CONSERVATION DIVISION
Wichita, Kansas
12-21-71

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Gatlin of Anadarko has this

date requested permission to plug the following described well:

Mr. Gatlin guarantees payment of the plugging fee.

Operator's full Name: Anadarko Production Co.

Complete Address: Box 351, Liberal, Kansas

Lease Name: Linscott "B" Well No. 2

Location: App C N/2 SW Sec. 32 Twp. 34 Rge. 43 (W)

County: Morton Total Depth 4630' Oil Well X

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Gatlin was instructed to plug the well as follows:

8 5/8" to 1242' circulated w/ cement. 4 1/2" to 4260' cemented.

Top perforations 4196' Plug bottom w/ 25 sacks cement.

Top of cement 3600' Mud 3600' to 1000'

Spot 35 sacks cement 1000' to 900' Mud 900' to 45'

Plug, Halls & 15 sacks cement 45' to 0'. Co. Pump

Very truly yours,

Conservation Division Agent