

State of Kansas



State Corporation Commission

CONSERVATION DIVISION

WM. H. AVERY Governor
WILLIAM L. MITCHELL Chairman
JAMES O. GREENLEAF Commissioner
HARRY G. WILES Commissioner
RAYMOND B. HARVEY Secretary
E. EDWARD JOHNSON Gen. Counsel

(Oil, Gas and Water)
500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

RECEIVED
STATE CORPORATION COMMISSION
JUL 8 1969
CONSERVATION DIVISION
Wichita, Kansas

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

J. P. Roberts
Administrator
500 Insurance Building
Wichita 2, Kansas

Dear Sir:

Mr. Gatlin of Anadarko Prod. has this
date requested permission to plug the following described well:

Mr. Gatlin guarantees payment of the plugging fee.

Operator's full Name: Anadarko Production Company

Complete Address: Box 351, Liberal, Kansas

Lease Name: Linscott "B" Well No. 1

Location: C SE Sec. 32 Twp. 34 Rge. 43 (E) (W)

County Morton Total Depth 3035' Oil Well

Gas Well X Input Well SWD Well D & A X Lost Hole

Mr. Gatlin was instructed to plug the well as follows:

8 5/8" to 596' circulated w/ cement. 4 1/2" to 2940' cemented.

Top perforations 2801' Plug bottom w/ 15 sacks cement

Top of cement 2600' Mud 2600' to 600'

Spot 35 sacks cement 600' to 500' Mud 500' to 40'

Plug, Halls & 10 sacks cement 40' to 0'.

Very truly yours,

Edgar J. Eves
Conservation Division Agent