

15-129-10582-0004

State of Kansas



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)RECEIVED
STATE CORPORATION COMMISSION
DEC 14 1971
CONSERVATION DIVISION
Wichita, KansasJ. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Gatlin of Anadarko Prod. has this

date requested permission to plug the following described well:

Mr. Gatlin guarantees payment of the plugging fee.Operator's full Name: Anadarko Production CompanyComplete Address: Box 351, Liberal, KansasLease Name: Interstate Unit Well No. 55Location: C SE NE Sec. 30 Twp. 34 Rge. 43 (E) (W)County: Morton Total Depth 4600' Oil Well XGas Well Input Well SWD Well D & A X Lost Hole Mr. Gatlin was instructed to plug the well as follows:8 5/8" to 1208' circulated w/ cement. 3 1/2" to 4600' cemented.Top perforations 4211' Plug bottom w/ 25 sacks cement.Top of cement 3000' Mud 3000' to 1000'Spot 35 sacks cement 1000' to 900' Mud 900' to 45'Plug, Halls & 15 sacks cement 45' to 0'.

Very truly yours,

Conservation Division Agent