

State of Kansas



WM. H. AVERY Governor
WILLIAM L. MITCHELL Chairman
JAMES O. GREENLEAF Commissioner
HARRY G. WILES Commissioner
RAYMOND B. HARVEY Secretary
E. EDWARD JOHNSON Gen. Counsel

State Corporation Commission
CONSERVATION DIVISION

(Oil, Gas and Water)
500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

FEB 17 1967

2-17-67

RECEIVED
CONSERVATION DIVISION
WICHITA, KANSAS

J. P. Roberts
Administrator
500 Insurance Building
Wichita 2, Kansas

Dear Sir:

Mr. Wilson of Ashland Oil & Refining has this

date requested permission to plug the following described well:

Mr. Wilson guarantees payment of the plugging fee.

Operator's full Name: Ashland Oil & Refining Company

Complete Address: 720 N.W. 50th St. Oklahoma City, Oklahoma

Lease Name: Theis Well No. 2

Location: C NE SW Sec. 5 Twp. 35 Rge. 25 (W)

County Clark Total Depth 6045' Oil Well

Gas Well X Input Well SWD Well D & A X Lost Hole

Mr. Wilson was instructed to plug the well as follows:

8 5/8" to 542' circulated w/ cement. 4 1/2" to 6039' cemented.

Plug Bottom w/ Bridge plug & 2 sacks cement. Top of cement 5625'

Mud 5625' to 540' Spotted 35 sacks cement 540' to 440'

Mud 440' to 40' Plug, Halls & 10 sacks cement 40' to 0'

Very truly yours,

Edward J. Evers
Conservation Division Agent