

State of Kansas



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION
DEC 22 1969
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Bentley of J.M. Huber has this

date requested permission to plug the following described well:

Mr. Bentley guarantees payment of the plugging fee.

Operator's full Name: J. M. Huber Corporation

Complete Address: Box 911, Amarillo, Texas

Lease Name: Government (RC) Well No. 2

Location: C N/2 NE Sec. 17 Twp. 34 Rge. 43 (E) (W)

County: Morton Total Depth 1356' Oil Well

Gas Well X Input Well SWD Well D & A X Lost Hole

Mr. Bentley was instructed to plug the well as follows:

4 1/2" to 1356' circulated w/ cement. Top perforations 1335'

Plug bottom w/ 15 sacks cement. Top of cement 1176'

Mud 1176' to 600' Spotted 15 sacks cement 600' to 420'

Mud 420' to 65' Plug & 5 sacks cement 65' to 0'.

\$/

Very truly yours,


Conservation Division Agent