

State of Kansas



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION
DEC 22 1969
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Bentley of J.M. Huber has this

date requested permission to plug the following described well:

Mr. Bentley guarantees payment of the plugging fee.Operator's full Name: J.M. Huber CorporationComplete Address: Box 911, Amarillo, Texas 79105Lease Name: Austin (RC) Well No. 2Location: NW SE SW Sec. 10 Twp. 34 Rge. 43 (E) (W)County: Morton Total Depth 1370' Oil Well Gas Well X Input Well SWD Well D & A X Lost Hole Mr. Bentley was instructed to plug the well as follows:

4 1/2" to 1367' circulated w/ cement. Top perforations 1297'

Plug bottom w/ 15 sacks cement Top of cement 1148'

Mud 1148' to 600' Spotted 15 sacks cement 600' to 420'.

Mud 420' to 65' Plug & 5 sacks cement 65' to 0'.

Very truly yours,

Edgar J. Gies
Conservation Division Agent