

15-175-00061-0000

State of Kansas



# State Corporation Commission

## CONSERVATION DIVISION

(Oil, Gas and Water)

P.O. Box 17027 3830 S. Meridian

WICHITA, KANSAS RECEIVED  
STATE CORPORATION COMMISSION

APR 10 1974

CONSERVATION DIVISION  
Wichita, Kansas

VERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)

J. Lewis Brock  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

Dear Sir:

Mr. Wilson of An-Son has this

date requested permission to plug the following described well:

Mr. Wilson guarantees payment of the plugging fee.

Operator's full Name: An-Son Corporations

Complete Address: 3814 N. Santa Fe, Oklahoma City, Oklahoma

Lease Name: Fincham Well No. 1

Location: C SE NW Sec. 3 Twp. 35 Rge. 33 XX (E) (W)

County: Seward Total Depth 6304' Oil Well

Gas Well X Input Well      SWD Well      D & A      Lost Hole     

Mr. Wilson was instructed to plug the well as follows:

8 5/8" to 1576' circulated w/ cement. 4 1/2" to 6302' cemented.


Topperforations 6218' Plug bottom w/ 35 sacks cement.

Top of cement 6100' Mud 6100' to 1625'

Spot 50 sacks cement 1625' to 1525' Mud 1525' to 40'

Plug, Halls & 10 sacks cement 40' to 0'.

Very truly yours,

  
Conservation Division Agent