

15-119-20099-0000

State of Kansas



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION
MAY 30 1972 5-30-72
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Dublin of Underwood has this

date requested permission to plug the following described well:

Mr. Dublin guarantees payment of the plugging fee.

Operator's full Name: Underwood Oil Company

Complete Address: 420 Oil & Gas Bldg., Wichita Falls, Texas

Lease Name: Jesse S. Adams Well No. 7-D

Location: 1980' FWL & 660' FSL Sec. 13 Twp. 35 Rge. 29 XX (E) (W)

County: Meade Total Depth 4598' Oil Well

Gas Well Input Well SWD Well D & A Lost Hole

Mr. Dublin was instructed to plug the well as follows:

8 5/8" to 1572' circulated w/ cement. Mud 4598' to 1500'

Spot 35 sacks cement 1500' to 1400' Mud 1400' to 45'

Plug, Hulls & 15 sacks cement 45' to 0'.

Very truly yours,

Conservation Division Agent