

State of Kansas



FORM CP-2

JOHN CARLIN
R. C. LOUX
JANE T. ROY
PHILLIP R. DICK
CAROL J. LARSON

Governor
Chairman
Commissioner
Commissioner
Executive Secretary

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

200 Colorado Derby Building
WICHITA, KANSAS 67202

VERBAL PERMIT FORM (To be filed by Plugging Agent)

Dear Sir:

Mr. Mike Godfrey of Raines & Williamson Oil Co. has this date requested permission to plug the following described well:

Operator's Full Name: Milson Enterprise Inc.

Complete Address: 1675 Broadway, Suite 2770 Denver Colo. 80202

Lease Name: Adams Well No. 1-8

Location: SW-SE Sec. 8 Twp. 35 Rge. 29W (E) (M)

County: Meade Total Depth: 6375

Abandoned Oil Well Gas Well Input Well SWD Well D&A

Other well as hereafter indicated: _____

Mr. Godfrey was instructed to plug the well as follows:

There is 1502' of 8 5/8" surface casing cement circulated. 1st plug 1530' with hole full of heavy mud with 40 lbs of cement pumped to 1530'. 2nd plug pushed rubber plug to 1200' the pumped 35 lbs of cement on top of rubber plug. 3rd plug on solid bridge 40' to 0' with 10 lbs of cement. Then put 5 lbs of cement in each rat hole & mouse hole. The plugging accomplished by Halliburton Co. of Liberal Kansas Carlile water well service Inc. of Box AA Liberal Kansas 67501. Will plug water well & file with corp. comm.

Very truly yours,

Paul Luttin
Conservation Division Agent

RECEIVED
STATE CORPORATION COMMISSION

NOV - 2 1981

CONSERVATION DIVISION
Wichita, Kansas