

State of Kansas



WM. H. AVERY Governor  
WILLIAM L. MITCHELL Chairman  
JOHN C. WOELK Commissioner  
HARRY G. WILES Commissioner  
RAYMOND B. HARVEY Secretary  
E. EDWARD JOHNSON Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)  
500 Insurance Bldg. 212 N. Market  
WICHITA, KANSAS 67202

VERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)

RECEIVED  
STATE CORPORATION COMMISSION  
MAY 13 1968  
CONSERVATION DIVISION  
Wichita, Kansas

J. P. Roberts  
Administrator  
500 Insurance Building  
Wichita 2, Kansas

Dear Sir:

Mr. Sargent of Mobley McCain has this

date requested permission to plug the following described well:

Mr. Sargent guarantees payment of the plugging fee.

Operator's full Name: Mobley McCain Winwell Exploration Company

Complete Address: 1011 Commerce Natl. Bk. Bldg., Shreveport, Louisiana

Lease Name: H.G. Adams Well No. 1-A

Location: NE SE Sec. 6 Twp. 35 Rge. 29 (W)

County Meade Total Depth 6529' Oil Well     

Gas Well X Input Well      SWD Well      D & A X Lost Hole     

Mr. Sargent was instructed to plug the well as follows:

8 5/8" to 1332' circulated w/ cement. 4 1/2" to 6525' cemented

Top perforations 6395' Plug bottom w/ 15 sacks cement.

Top of cement 6250' Mud 6250' to 800'

Spotted 35 sacks cement 800' to 700' Mud 700' to 45'

Plug, Halls & 15 sacks cement 45' to 0'

Very truly yours,

Edward J. Eves  
Conservation Division Agent