

STATE OF KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION
200 Colorado Derby Building
Wichita, Kansas 67202

FORM CP-1
Rev. 6/4/84

WELL PLUGGING APPLICATION FORM
(File One Copy)

API NUMBER 15-175-20,614 ~~0000~~ (of this well) 6/88
(This must be listed; if no API# was issued, please note drilling completion date.)

LEASE OPERATOR Sage Drilling Co., Inc. OPERATORS LICENSE NO. 5421

ADDRESS 202 S. St. Francis, Wichita, Ks 67202 PHONE # (316) 263-6139

LEASE (FARM) Black WELL NO. 2-1 WELL LOCATION C SE NW COUNTY Seward

SEC. 1 TWP. 34S RGE. 31 (E) or (W) TOTAL DEPTH 6040 PLUG BACK TD 5600 (CIBP)

Check One:

OIL WELL GAS WELL D & A SWD or INJ WELL DOCKET NO. _____

SURFACE CASING SIZE 8 5/8" SET AT 1564 CEMENTED WITH 780 SACKS

CASING SIZE 5 1/2" SET AT 6039 CEMENTED WITH 100 SACKS

PERFORATED AT 5962-65, 5969-73/ CIBP @ 5958', 5924-27, 5934-43, 5947-52, CIBP 5723-78,
CIBP 4323-31 (open now)
@5600' 100 Sx DV Tool @5900'

CONDITION OF WELL: GOOD POOR CASING LEAK JUNK IN HOLE

OPERATOR'S SUGGESTED METHOD OF PLUGGING THIS WELL (1) Pump 2 sx of hulls followed by 30 sx of cmt
with 9 ppg mud (2) Cut off 5 1/2" Csg at +/- 2800' (3) Fill hole with mud to 1600' (4) 50 sx Cmt plug
from 1600' to 1430' (5) The well will be turned into Cedar Hills SWD well so an 8 5/8" CIBP and
10' of cmt on top of it (if additional space is needed use back of form)
will be set above 1430' to insure no fluid will go down hole.

IS WELL LOG ATTACHED TO THIS APPLICATION AS REQUIRED? Only small IS ACO-1 FILED? yes
(If not, explain) scale

Dual Ind. Log -no other extra log copies

DATE AND HOUR PLUGGING IS DESIRED TO BEGIN March 15, 1988

PLUGGING OF THIS WELL WILL BE DONE IN ACCORDANCE WITH K.S.A. 55-101 et seq AND THE RULES AND REGULATIONS OF THE STATE CORPORATION COMMISSION.

NAME OF COMPANY REPRESENTATIVE AUTHORIZED TO BE IN CHARGE OF PLUGGING OPERATIONS:

Casey Coats PHONE # (316) 263-6139

ADDRESS 202 S. St. Francis, Wichita, Kansas 67202

PLUGGING CONTRACTOR Sargent's Casing Pulling Service LICENSE NO. 6547 6/88

ADDRESS Box 506, Liberal, Kansas 67901 PHONE # (316) 624-7455

PAYMENT WILL BE GUARANTEED BY OPERATOR OR AGENT SIGNED: Casey Coats RECEIVED
(Operator or Agent) STATE CORPORATION COMMISSION

DATE: 2/19/88 77 2 9 1988

15-175-20614-0000

State of Kansas



Kansas Corporation Commission

MIKE HAYDEN GOVERNOR
KEITH R. HENLEY CHAIRMAN
RICH KOWALEWSKI COMMISSIONER
MARGALEE WRIGHT COMMISSIONER
JUDITH McCONNELL EXECUTIVE DIRECTOR
FRANK A. CARO, JR. GENERAL COUNSEL

CONSERVATION DIVISION
SHARI M. FEIST, DIRECTOR
200 Colorado Derby Bldg.
202 W. 1st Street
Wichita, KS 67202-1286
(316) 263-3238

THIS NOTICE
JUN 9 '88
EXPIRES

March 9, 1988

WELL PLUGGING NOTICE

Black #2-1
C SE NW
Sec. 01-34S-31W
Seward County

Sage Drilling Company, Inc.
202 S. St. Francis
Wichita, KS 67202

Gentlemen:

This is your notice to plug the above subject well in accordance with the Rules and Regulations of the State Corporation Commission.

Please contact the district office listed below to review your suggested method of plugging five days prior to plugging the well (KAR-82-3-113).

This notice is void after ninety (90) days from the above date.

Sincerely,

Shari Feist

Shari Feist
Director
State Corporation Commission

DISTRICT #1 302 W. McArtor, Dodge City, KS 67801 (316) 225-6760