

STATE OF KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION
200 Colorado Derby Building
Wichita, Kansas 67202

FORM CP-1
Rev. 6/4/84

WELL PLUGGING APPLICATION FORM
(File One Copy)

API NUMBER 15-175-20,620-0000 (of this well) 6/86
(This must be listed; if no API# was issued, please note drilling completion date.)

LEASE OPERATOR Sage Drilling Co., Inc. OPERATORS LICENSE NO. 5421

ADDRESS 202 S. St. Francis, Wichita, KS 67202 PHONE # (316) 263-6139

LEASE (FARM) Black WELL NO. 3-1 WELL LOCATION C NW SW COUNTY Seward

SEC. 1 TWP. 34S RGE. 31 or (W) TOTAL DEPTH 6100 PLUG BACK TD 5910

Check One:

OIL WELL _____ GAS WELL D & A _____ SWD or INJ WELL _____ DOCKET NO. _____

SURFACE CASING SIZE 8-5/8" SET AT 1549 CEMENTED WITH 700 SACKS

CASING SIZE 5 1/2" SET AT 6099 CEMENTED WITH 150 SACKS (TOC=3664')

PERFORATED AT 5686-92', 5704-06', 5710-13' (Morrow) Present; past: 5953-62' below CIBP;
4330-40"; 4344-47" (squeezed off)

CONDITION OF WELL: GOOD POOR _____ CASING LEAK _____ JUNK IN HOLE _____

OPERATOR'S SUGGESTED METHOD OF PLUGGING THIS WELL (1) Pump 2 sx hulls followed by 30 sx. cement down casing w/9 ppg mud (2) Pull free 5 1/2" casing (3) Set 50 sx. cement plug at 1600' w/5 1/2" casing (4) set 50 sx. cement plug at 550' w/5 1/2" casing (5) 20 sx. cement plug at 40'-0' (6) Cut off and cap 8-5/8" casing.

(If additional space is needed use back of form)

IS WELL LOG ATTACHED TO THIS APPLICATION AS REQUIRED? yes IS ACO-1 FILED? yes
(If not, explain)

DATE AND HOUR PLUGGING IS DESIRED TO BEGIN May 5, 1986

PLUGGING OF THIS WELL WILL BE DONE IN ACCORDANCE WITH K.S.A. 55-101 et seq AND THE RULES AND REGULATIONS OF THE STATE CORPORATION COMMISSION.

NAME OF COMPANY REPRESENTATIVE AUTHORIZED TO BE IN CHARGE OF PLUGGING OPERATIONS:

Casey Coats PHONE # (316) 263-6139

ADDRESS 202 S. St. Francis, Wichita, KS 67202

PLUGGING CONTRACTOR Sargent's Casing Pulling Service LICENSE NO. 6547

ADDRESS Box 506, Liberal, KS 67901 PHONE # (316) 624-7455

PAYMENT WILL BE GUARANTEED BY OPERATOR OR AGENT SIGNED: Casey Coats
(Operator or Agent)

STATE CORPORATION COMMISSION

MAR 10 1986

DATE: March 13, 1986

CONSERVATION DIVISION
Wichita, Kansas



JOHN CARLIN
MICHAEL LENNEN
MARGALEE WRIGHT
KEITH R. HENLEY
JUDITH A. McCONNELL
BRIAN J. MOLINE

Governor
Chairman
Commissioner
Commissioner
Executive Secretary
General Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
200 Colorado Derby Building
202 West 1st Street
WICHITA, KANSAS 67202-1286

THIS NOTICE

JUN 19 1986

EXPIRES

March 19, 1986

WELL PLUGGING NOTICE

Black #3-1
C NW SW
Sec. 1-34S-31W
Seward County

Sage Drilling Company, Inc.
202 S. St. Francis
Wichita, KS 67202

Gentlemen:

This is your notice to plug the above subject well in accordance with the Rules and Regulations of the State Corporation Commission.

This notice is void after ninety (90) days from the above date.

Sincerely,

William R. Bryson, Director

Please contact the district office to review your suggested method of plugging

DIST. #1 302 West McArtor Dodge City, KS 67801 316-225-6760

five days prior to plugging the well (KAR-82-3-113).