

STATE OF KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION
200 Colorado Derby Building
Wichita, Kansas 67202

FORM CP-1
Rev. 6/4/84

RECEIVED
STATE CORPORATION COMMISSION

APR 29 1991

WELL PLUGGING APPLICATION FORM
(File One Copy)

CONSERVATION DIVISION
Wichita, Kansas

API NUMBER 15-175-20,891-000 (of this well)
(This must be listed; if no API# was issued, please note drilling completion date.)

LEASE OPERATOR Chaparral Energy, Inc. OPERATORS LICENSE NO. 30051

ADDRESS 10701 N. Broadway Ext., Oklahoma City, OK 73114 PHONE # (405) 749-9992

LEASE (FARM) Stefan WELL NO. 1-21 WELL LOCATION C-SE-NW COUNTY Seward

SEC. 21 TWP. 34S RGE. 32W (E) or (W) TOTAL DEPTH 6,200' PLUG BACK TD 5,961'

Check One:

OIL WELL _____ GAS WELL X D & A _____ SWD or INJ WELL _____ DOCKET NO. _____

SURFACE CASING SIZE 8 5/8" SET AT 1,557' CEMENTED WITH 1400 SACKS

CASING SIZE 4 1/2" SET AT 6,200' CEMENTED WITH 305 SACKS

PERFORATED AT 5,798'-5,806' and 5,968'-5,972'

CONDITION OF WELL: GOOD X POOR _____ CASING LEAK _____ JUNK IN HOLE _____

OPERATOR'S SUGGESTED METHOD OF PLUGGING THIS WELL Set CIBP @ 5,725'. Dump 2 sacks cement on top of Bridge Plug. Cut off 4 1/2" Csg. and pull. Pump 300 sacks hulls, 15 sacks gel, 50 sacks cement, 10 sacks gel, 100# hulls, 8 5/8" wiper plug and 175 sacks cement down 8 5/8" csg.
(If additional space is needed use back of form)

IS WELL LOG ATTACHED TO THIS APPLICATION AS REQUIRED? N0-filed w/ IS ACO-1 FILED? yes
(If not, explain)

DATE AND HOUR PLUGGING IS DESIRED TO BEGIN 05/01/91 8:00 a.m. (Contractor will call Dodge City)

PLUGGING OF THIS WELL WILL BE DONE IN ACCORDANCE WITH K.S.A. 55-101 et seq AND THE RULES AND REGULATIONS OF THE STATE CORPORATION COMMISSION.

NAME OF COMPANY REPRESENTATIVE AUTHORIZED TO BE IN CHARGE OF PLUGGING OPERATIONS:

Mark A. Fischer PHONE # (405) 749-9992

ADDRESS 10701 N. Broadway Ext., Oklahoma City, Oklahoma 73114

PLUGGING CONTRACTOR Midwest Casing Pulling LICENSE NO. 6497

ADDRESS Box F, Sublette, KS 67877 PHONE # (316) 276-3286

PAYMENT WILL BE GUARANTEED BY OPERATOR OR AGENT SIGNED: Mark A. Fischer
(Operator or Agent)

DATE: April 25, 1991



Kansas Corporation Commission

Joan Finney
Governor

Jim Robinson
Chairman

Keith R. Henley
Commissioner

Rachel C. Lipman
Commissioner

Judith McConnell
Executive Director

Brian J. Moline
General Counsel

NOTICE OF RECEIPT OF WELL PLUGGING APPLICATION

May 3, 1991

Chaparral Energy, Inc.
10701 B. Broadway Ext.
Oklahoma City, OK 73114

Stefan 1-21
API 15-175-20,891
C SE SW
Sec. 21-34-32W
Seward County

Dear Operator:

This letter is to notify you that the Conservation Division is in receipt of your plugging proposal, form CP-1, for the above-captioned well.

Your CP-1 has been reviewed by the Conservation Division central office for completeness and to verify license numbers. The plugging proposal will now be forwarded to the district office listed below for review of your proposed method of plugging. Please contact the district office for approval of your proposed plugging method at least at five (5) days before plugging the well, pursuant to K.A.R. 82-3-113 (b). Failure to do so is punishable by an administrative penalty of up to \$1000.

It has recently come to my attention that the form CP-1 has been filed by operators other than the owner or operator of the well and without the consent of the owner or operator. The Conservation Division's review of form-CP-1, either in the central or district office, does not include an inquiry into well ownership or the filing operator's legal right to plug the well.

This notice in no way constitutes authorization to plug the above-captioned well by persons not having legal rights of ownership or interest in the well. This notice is void after ninety (90) days from the above date.

Sincerely,

David P. Williams
Production Supervisor

Conservation Division
William R. Bryson
Director
200 Colorado Derby Bldg.
202 W. 1st Street
Wichita, Kansas 67202-1286
Telephone (316) 263-3238

District: #1 304 W. McArtor
Dodge City, KS 67801
(316) 225-6760