

**KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING APPLICATION**
Please TYPE Form and File ONE Copy

Form CP-1
September 2003
This Form must be Typed
Form must be Signed
All blanks must be Filled

API # 15 - 189-22450 - 00 - 60 (Identifier Number of this well). This must be listed for wells drilled since 1967; if no API # was issued,

indicate original spud or completion date 7/18/03

Well Operator: Anadarko Petroleum Corp. KCC License #: 4549 8/04
(Owner / Company Name) (Operator's)

Address: 1201 Lake Robbins Dr City: The Woodlands

State: Texas Zip Code: 77380 Contact Phone: (832) 636 - 3127

Lease: HJV Dudley "A" Well #: 1 Sec. 21 Twp. 32 S. R. 38 East West

- SW - SW - NW Spot Location / QQQQ County: Stevens

2310 Feet (in exact footage) From North / South (from nearest outside section corner) Line of Section (Not Lease Line)

330 Feet (in exact footage) From East / West (from nearest outside section corner) Line of Section (Not Lease Line)

Check One: Oil Well Gas Well D&A Cathodic Water Supply Well
 SWD Docket # _____ ENHR Docket # _____ Other: _____

Conductor Casing Size: _____ Set at: _____ Cemented with: _____

Surface Casing Size: 8-5/8 Set at: 1775 Cemented with: 535

Production Casing Size: 5-1/2 Set at: 6408 Cemented with: 145

List (ALL) Perforations and Bridgeplug Sets: 6294'-6301', CIBP @ 6280', 6061'-6069'

Elevation: 3201' (G.L. / K.B.) T.D.: 6415' PBDT: 6347' Anhydrite Depth: _____
(Stone Corral Formation)

Condition of Well: Good Poor Casing Leak Junk in Hole

Proposed Method of Plugging (attach a separate page if additional space is needed): Bullhead 2 sxs hulls and 20 sx Class H neat cement plug from 5910' to 6069' followed with 9 ppg mud. Shoot off 5-1/2" casing at freepoint. Spot 50 sxs Class H neat cement from 1825' to 1677'. Spot 40 sxs Class H from 600' to 479'. Spot 10 sxs from 40' to 4'. Cut off and cap 8-5/8" below surface.

Is Well Log attached to this application as required? Yes No Is ACO-1 filed? Yes No

If not explain why? Log filed with original ACO-1

Plugging of this Well will be done in accordance with K.S.A. 55-101 et. seq. and the Rules and Regulations of the State Corporation Commission.

List Name of Company Representative authorized to be in charge of plugging operations: Dawn Nease

Phone: (620) 544 - 6201


Address: P.O. Box 40 City / State: Hugoton, KS 67951

Plugging Contractor: Sargent & Horton Plugging, Inc. KCC License #: 31151 11/30/04
(Company Name) (Contractor's)

Address: Rt. 1, Box 49BA, Tyrone, OK 73951-9731 Phone: (405) 854 - 6515

Proposed Date and Hour of Plugging (if known?): Friday, October 24

Payment of the Plugging Fee (K.A.R. 82-3-118) will be guaranteed by Operator or Agent

Date: 10/22/03 Authorized Operator / Agent: 
(Signature)

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

RECEIVED
KANSAS CORPORATION COMMISSION
OCT 23 2003
CONSERVATION DIVISION
WICHITA, KS

KANSAS

CORPORATION COMMISSION

Kathleen Sebelius, Governor Brian J. Moline, Chair John Wine, Commissioner Robert E. Krehbiel, Commissioner

NOTICE OF RECEIPT OF WELL PLUGGING APPLICATION (CP-1)

Anadarko Petroleum Corporation
1201 Lake Robbins Drive
The Woodlands, TX 77380

October 24, 2003

Re: HJV DUDLEY A #1
API 15-189-22450-00-00
SWSWNW 21-32S-38W, 2310 FNL 330 FWL
STEVENS COUNTY, KANSAS

Dear Operator:

This letter is to notify you that the Conservation Division is in receipt of your plugging proposal, form CP-1, for the above-captioned well.

Your CP-1 has been reviewed by the Conservation Division central office for completeness and to verify license numbers. The plugging proposal will now be forwarded to the district office listed below for review of your proposed method of plugging.

Please contact the district office for approval of your proposed plugging method at least five (5) days before plugging the well, pursuant to K.A.R. 82-3-113 (b). If a workover pit will be used during the plugging of the well it must be permitted. A CDP-1 form must be filed and approved prior to the use of the pit.

The Conservation Division's review of form CP-1, either in the central or district office, does not include an inquiry into well ownership or the filing operator's legal right to plug the well.

This notice in no way constitutes authorization to plug the above-captioned well by persons not having legal rights of ownership or interest in the well. This notice is void after ninety (90) days from the above date.

Sincerely



David P. Williams
Production Supervisor

District: #1
210 E Frontview, Suite A
Dodge City, KS 67801
(316) 225-8888