

STATE OF KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION
200 Colorado Derby Building
Wichita, Kansas 67202

FORM CP-1
Rev. 6/4/84

WELL PLUGGING APPLICATION FORM
(File One Copy)

API NUMBER 15-175-20,781-60-00 (of this well)

(This must be listed; if no API# was issued, please note drilling completion date.)

LEASE OPERATOR Donald C. Slawson OPERATORS LICENSE NO. 5181

ADDRESS Suite 700, 20 N. Broadway, Okla. City, OK 73102 PHONE # (405) 232-0201

LEASE (FARM) DAVIES WELL NO. 1-23 WELL LOCATION SW SW COUNTY Seward

SEC. 23 TWP. 34S RGE. 32 ~~EX~~ or (W) TOTAL DEPTH 6,200' PLUG BACK TO N/A

Check One:

OIL WELL GAS WELL D & A X SWD or INJ WELL DOCKET NO.

SURFACE CASING SIZE 8-5/8" SET AT 1,558' CEMENTED WITH 800 SACKS

CASING SIZE 4-1/2" SET AT 4,778' CEMENTED WITH 200 SACKS

PERFORATED AT 4,522' - 4,525'

CONDITION OF WELL: GOOD POOR CASING LEAK JUNK IN HOLE

OPERATOR'S SUGGESTED METHOD OF PLUGGING THIS WELL Set CIBP @ 4,465', cap w/20' cement. Shoot

Casing @ 3,023', spot 50 sx cement 2,600' - 2,500'. Displace hole w/9 ppg mud. TOH to 1,550'.

Spot 50 sx cement 1,550' - 1,450'. TOH to 800'. Spot 50 sx cement 800' - 700'. TOH. Spot 10

(If additional space is needed use back of form)

IS WELL LOG ATTACHED TO THIS APPLICATION AS REQUIRED? yes IS ACO-1 FILED? attached
(If not, explain)

DATE AND HOUR PLUGGING IS DESIRED TO BEGIN 8/22/85

PLUGGING OF THIS WELL WILL BE DONE IN ACCORDANCE WITH K.S.A. 55-101 et seq AND THE RULES AND REGULATIONS OF THE STATE CORPORATION COMMISSION.

NAME OF COMPANY REPRESENTATIVE AUTHORIZED TO BE IN CHARGE OF PLUGGING OPERATIONS:

Daniel G. Wilson PHONE # (405) 232-0201

ADDRESS Suite 700, 20 N. Broadway, Oklahoma City, OK 73102

PLUGGING CONTRACTOR Sargent's Casing Pulling Service LICENSE NO. 6547

ADDRESS 620 S. Lincoln, Liberal, KS 67901 PHONE # (316) 624-7455

PAYMENT WILL BE GUARANTEED BY OPERATOR OR AGENT SIGNED: Daniel G. Wilson

RECEIVED
STATE CORPORATION COMMISSION

(Operator or Agent)

Daniel G. Wilson

SEP 12 1985

DATE:

9/3/85