



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

P.O. Box 17027 3830 S. Meridian
WICHITA, KANSAS 67217

VERBAL PERMIT FORM (To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION
JUN 12 1974
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Peters of Ascot has this

date requested permission to plug the following described well:

Mr. Peters guarantees payment of the plugging fee.

Operator's full Name: Ascot Oil Inc.

Complete Address: Box 5248, Shreveport, La.

Lease Name: Shaw Well No. 1

Location: C NW Sec. 10 Twp. 34 Rge. 23 ^{XX} (E) (W)

County: Clark Total Depth 6500' Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Peters was instructed to plug the well as follows:


8 5/8" to 404' circulated w/ cement. Mud 6500' to 700'

Spot 30 sacks cement 700' to 600' Mud 600' to 400'

Spot 30 sacks cement 400' to 300' Mud 300' to 45'

Plug, Halls & 15 sacks cement 45' to 0'.

Very truly yours,


Conservation Division Agent