

State of Kansas



JOHN ANDERSON, Jr. Governor
WILLIAM L. MITCHELL, Chairman
ALVIN F. GRAUERHOLZ Commissioner
HARRY G. WILES Commissioner
RAYMOND B. HARVEY Secretary
ROBT. C. LONDERHOLM Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION
MAR 25 1965
3-25-65
CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Adminstrator
500 Insurance Building
Wichita 2, Kansas

Dear Sir:

Mr. Michaelis of Graham-Michaelis Drilling Co. on this

date requested permission to plug the following described well:

Mr. Michaelis guarantees payment of the plugging fee.

Operator's full Name: Graham-Michaelis Drilling Co.

Complete Address: Box 1294 Liberal, Kansas

Lease Name: Randall Well No. # 1-26

Location: C SE/4 Sec. 26 Twp. 34S Rge. 22 (E/W)

County Clark Total Depth 5724' Oil Well

Gas Well X Input Well SWD Well D & A X Lost Hole

Mr. Michaelis was instructed to plug the well as follows:

8 5/8"-750' Circulated w/cement. 4 1/2"-5724' Cemented.

Perforations 5534' to 5572' Plug bottom w/20 Sax. cement top cement 5400'

Mud 5400' to 700' Spotted 35 Sax. cement 700' to 600'

Mud 600' to 45' Plug, Hulls, 15 Sax. cement 45' to 0

Very truly yours,

[Signature]
Conservation Division Agent