



JOHN ANDERSON, Jr. Governor
 RICHARD C. BYRD Chairman
 ALVIN F. GRAUERHOLZ Commissioner
 HARRY G. WILES Commissioner
 RAYMOND B. HARVEY Secretary
 CHARLES C. McCARTER Gen. Counsel

State Corporation Commission
 CONSERVATION DIVISION
 (Oil, Gas and Water)
 500 Insurance Bldg. 212 N. Market
 WICHITA, KANSAS

VERBAL PERMIT FORM
 (To Be Filed By Plugging Agent)

RECEIVED
 STATE CORPORATION COMMISSION

JUL 29 1963

CONSERVATION DIVISION
 Wichita, Kansas

J. P. Roberts
 Assistant Director
 500 Insurance Building
 212 North Market
 Wichita 2, Kansas

Dear Sir:

Mr. Shiftner of Skelly Oil Company has this date requested permission to plug the following described well:

Mr. Shiftner guarantees payment of the plugging fee.

Operator's full Name: Skelly Oil Company

Complete Address: Box 649 Mc/Cook, Nebraska

Lease Name: Cordes Well No. # 1

Location: NW/4 NW/4 NW/4 Sec. 36 Twp. 33 Rge. 29 (E) (W)

County Meade Total Depth 5860' Oil Well X

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Shiftner was instructed to plug the well as follows:

8 5/8" 1452' Circulated w/cement. 5 1/2" Cemented. Plug Back to 5726"

Top Perforations-5690'

Sand 5726' to 5675' 20 Sax.cement 5675' to 5535'

Mud 5535' to 685' Rock Bridge 685' to 667'

35 Sax.cement 667' to 567' Mud 567' to 40'

Rock Bridge 40' to 30' 10 ax.cement 30' to surface.

[Signature]
 Conservation Division Agent