

State of Kansas



WM. H. AVERY Governor  
WILLIAM L. MITCHELL Chairman  
JAMES O. GREENLEAF Commissioner  
HARRY G. WILES Commissioner  
RAYMOND B. HARVEY Secretary  
E. EDWARD JOHNSON Gen. Counsel

### State Corporation Commission

#### CONSERVATION DIVISION

(Oil, Gas and Water)  
500 Insurance Bldg. 212 N. Market  
WICHITA, KANSAS 67202

#### VERBAL PERMIT FORM (To Be Filed By Plugging Agent)

RECEIVED  
STATE CORPORATION COMMISSION  
JUL 29 1966  
7-29-66  
CONSERVATION DIVISION  
Wichita, Kansas

J. P. Roberts  
Administrator  
500 Insurance Building  
Wichita 2, Kansas

Dear Sir:

Mr. Michaelis of Graham-Michaelis Drlg. Co has this date requested permission to plug the following described well:

Mr. Michaelis guarantees payment of the plugging fee.

Operator's full Name: Graham-Michaelis Drilling, Inc.

Complete Address: 211 North Broadway, Wichita, Kansas

Lease Name: Randall Well No. 2-14

Location: 1320' S of NL 50 W of E1 Sec. 14 Twp. 34 Rge. 22 (E) (W)

County Clark Total Depth 5485' Oil Well X

Gas Well X Input Well      SWD Well      D & A X Lost Hole     

Mr. Michaelis was instructed to plug the well as follows:

8 5/8" to 628' circulated w/ cement. T.D. 5485'

Mud 5485' to 675' Spot 35 sacks cement 675' to 575'

Mud 575' to 45' Plug, Hulls & 15 sacks cement 45' to 0

Very truly yours,

Edgar J. Lewis  
Conservation Division Agent