

State of Kansas



# State Corporation Commission

## CONSERVATION DIVISION

(Oil, Gas and Water)  
500 Insurance Bldg. 212 N. Market  
WICHITA, KANSAS 67202

### VERBAL PERMIT FORM (To Be Filed By Plugging Agent)

RECEIVED  
STATE CORPORATION COMMISSION  
JAN 16 1973  
CONSERVATION DIVISION  
Wichita, Kansas

J. Lewis Brock  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

Dear Sir:

Mr. Sullivan of Rider has this

date requested permission to plug the following described well:

Mr. Sullivan guarantees payment of the plugging fee.

Operator's full Name: Don C. Rider Oil Operations

Complete Address: 104 W. Lockwood St. Medicine Lodge, Kansas

Lease Name: Grace E. Smith Well No. 1

Location: C NW Sec. 14 Twp. 34 Rge. 22 XX (E) (W)

County: Clark Total Depth 5700' Oil Well X

Gas Well      Input Well      SWD Well      D & A      Lost Hole     

Mr. Sullivan was instructed to plug the well as follows:

20" to 67' circulated w/ cement. 8 5/8" to 716' circulated w/ cement.

5 1/2" to 5700' cemented, Top perforations 5434'

Plug bottom w/ sand & 5 sacks cement. Top of cement 5350'

Mud 5350' to 550' Spot 35 sacks cement 550' to 450'

Mud 450' to 45' Plug, Halls & 15 sacks cement 45' to 0'.

Very truly yours,

Conservation Division Agent