

State of Kansas



WM. H. AVERY Governor  
WILLIAM L. MITCHELL Chairman  
JAMES O. GREENLEAF Commissioner  
HARRY G. WILES Commissioner  
RAYMOND B. HARVEY Secretary  
E. EDWARD JOHNSON Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)  
500 Insurance Bldg. 212 N. Market  
WICHITA, KANSAS 67202

VERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)

RECEIVED  
STATE CORPORATION COMMISSION

APR 20 1966

CONSERVATION DIVISION  
Wichita, Kansas

J. P. Roberts  
Administrator  
500 Insurance Building  
Wichita 2, Kansas

Dear Sir:

Mr. Dunkin of Ashland Oil & Refin. Co. has this  
date requested permission to plug the following described well:

Mr. Dunkin guarantees payment of the plugging fee.

Operator's full Name: Ashland Oil & Refining Company

Complete Address: P.O. Box 18695, Oklahoma, City Oklahoma

Lease Name: Harper-Randall Well No. 1

Location: App C S/2 N/2 SE Sec. 13 Twp. 34 Rge. 22 (E) (W)

County Clark Total Depth 5460' Oil Well X

Gas Well      Input Well      SWD Well      D & A X Lost Hole     

Mr. Dunkin was instructed to plug the well as follows:

8 5/8" to 567' Circulated w/ cement. 4 1/2" to 5331' Cemented.

Top perforations 5180' Plug bottom w/ 20 sacks cement.

Top of cement 5120' Mud 5120' to 610'

Spotted 35 sacks cement 610 to 510' Mud 510 to 45'

Plug, Huls & 15 sacks cement 45' to 0. Company Pump

Very truly yours,

Edgar H. Eves  
Conservation Division Agent