

State of Kansas



ROBERT B. DOCKING Governor  
 DALE E. SAFFELS Chairman  
 JULES V. DOTY Commissioner  
 JAMES O. GREENLEAF Commissioner  
 RAYMOND B. HARVEY Secretary  
 JACK GLAVES Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market  
WICHITA, KANSAS 67202

VERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)

RECEIVED  
 STATE CORPORATION COMMISSION  
 DEC 11 1968  
 CONSERVATION DIVISION  
 Wichita, Kansas

J. P. Roberts  
 Administrator  
 500 Insurance Building  
 Wichita, Kansas 67202

Dear Sir:

Mr. Sargent of Graham-Michaelis has this

date requested permission to plug the following described well:

Mr. Sargent guarantees payment of the plugging fee.

Operator's full Name: Graham-Michaelis Drilling Co.

Complete Address: Box 1294, Liberal, Kansas 67901

Lease Name: Carlson Well No. 1-10

Location: Center Sec. 10 Twp. 34 Rge. 22 (E) (W)

County: Clark Total Depth 5602' Oil Well

Gas Well X Input Well      SWD Well      D & A X Lost Hole     

Mr. Sargent was instructed to plug the well as follows:

8 5/8" to 621' circulated w/ cement. 4 1/2" to 5600' cemented

Top perforations 5438' Plug bottom w/ 20 sacks cement

Top of cement 5300' Mud 5300' to 650'

Spot 40 sacks cement 650' to 530' Mud 530' to 40'

Plug, Halls & 10 sacks cement 40' to 0'.

Very truly yours,

Edgar J. Evers  
 Conservation Division Agent