

State of Kansas



WM. H. AVERY Governor  
WILLIAM L. MITCHELL Chairman  
JAMES O. GREENLEAF Commissioner  
HARRY G. WILES Commissioner  
RAYMOND B. HARVEY Secretary  
E. EDWARD JOHNSON Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)  
500 Insurance Bldg. 212 N. Market  
WICHITA, KANSAS 67202

VERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)

RECEIVED  
STATE CORPORATION COMMISSION  
MAY 24 1966  
5-24-66  
CONSERVATION DIVISION  
Wichita, Kansas

J. P. Roberts  
Administrator  
500 Insurance Building  
Wichita 2, Kansas

Dear Sir:

Mr. Kelso of Sterling Drlg. Co. has this  
date requested permission to plug the following described well:

Mr. Kelso guarantees payment of the plugging fee.

Operator's full Name: Sterling Drilling Company

Complete Address: Box 127, Sterling, Kansas

Lease Name: Blackhall Well No. 1

Location: C SE Sec. 9 Twp. 34 Rge. 22 (E) (W)

County Clark Total Depth 5600' Oil Well

Gas Well  Input Well  SWD Well  D & A  Lost Hole

Mr. Kelso was instructed to plug the well as follows:

8 5/8" to 658' circulated w/ cement. 4 1/2" to 5599' cemented.

Top Perf. 5428' Plug bottom w/ 20 sacks cement.

Top of cement 5220' Mud 5220' to 700'

Spot 35 sacks cement 700' to 600' Mud 600' to 50'

Bridge & 15 sacks cement 50' to 0' Weld Plate on 8 5/8"

Very truly yours,

Edgar J. Eves  
Conservation Division Agent