

State of Kansas



JOHN ANDERSON, Jr. Governor
 RICHARD C. BYRD Chairman
 ALVIN F. GRAUERHOLZ Commissioner
 HARRY G. WILES Commissioner
 RAYMOND B. HARVEY Secretary
 CHARLES C. McCARTER Gen. Counsel

State Corporation Commission
 CONSERVATION DIVISION
 (Oil, Gas and Water)
 500 Insurance Bldg. 212 N. Market
 WICHITA, KANSAS

VERBAL PERMIT FORM
 (To Be Filed By Plugging Agent)

RECEIVED
 STATE CORPORATION COMMISSION

OCT 1 1962

CONSERVATION DIVISION
 Wichita, Kansas

J. P. Roberts
 Assistant Director
 500 Insurance Building
 212 North Market
 Wichita 2, Kansas

Dear Sir:

I have this date 21 September, 1962, authorized
 The following plugging operation:

Operator's full Name: Texaco Inc.

Complete Address: 614 Bitting Bldg., Wichita, Kansas

Lease Name: Campbell "B" Well No. # 1

Location: C SW NW Sec. 33 Twp. 34 Rge. 21 (E)(W)

County Clark Total Depth: 5694'

Oil Well Gas Well X Input Well SWD Well

D & A Other well as hereafter indicated:

Operator was instructed to plug well as follows:

13 3/8" 156' Cemented. 8 5/8" 601' Cemented.

4 1/2" 5694' Cemented. Top of perforation, 5520'

Plug bottom of hole to 5500'

Heavy mud 5500' to 600' Plug and 35 sax.cement at 600'

Heavy mud top of cement to 50' Plug and 15 sax.cement to surface.

Very truly yours,

