

State of Kansas



WM. H. AVERY Governor  
WILLIAM L. MITCHELL Chairman  
JOHN C. WOELK Commissioner  
HARRY G. WILES Commissioner  
RAYMOND B. HARVEY Secretary  
E. EDWARD JOHNSON Gen. Counsel

# State Corporation Commission

## CONSERVATION DIVISION

(Oil, Gas and Water)  
500 Insurance Bldg. 212 N. Market  
WICHITA, KANSAS 67202

### VERBAL PERMIT FORM (To Be Filed By Plugging Agent)

RECEIVED  
STATE CORPORATION COMMISSION  
JUN 3 1968  
CONSERVATION DIVISION  
Wichita, Kansas

J. P. Roberts  
Administrator  
500 Insurance Building  
Wichita 2, Kansas

Dear Sir:

Mr. Dellinger of Knight Casing Pulling has this date requested permission to plug the following described well:

Mr. Dellinger guarantees payment of the plugging fee.

Operator's full Name: Knight Casing Pulling Co.

Complete Address: Box 405, Chase, Kansas

Lease Name: Bentley Randell Well No. 1

Location: C SW NE Sec. 32 Twp. 34 Rge. 21 (X) (W)

County Clark Total Depth 5680' Oil Well     

Gas Well X Input Well      SWD Well      D & A X Lost Hole     

Mr. Dellinger was instructed to plug the well as follows:

30" to 27' circulated w/ cement.      20" to 220' circulated w/ cement.

10 3/4" tp 600' circulated w/ cement.      5 1/2" to 5620' cemented

Top perforations 5448'      Plug bottom w/ Sand & 5 sacks cement.

Top of cement 5330'      Mud 5330' to 500'

Rock bridge & 50 sacks cement 500' to 400'      Mud 400' to 45'

Rock bridge & 15 sacks cement 45' to 0'

Very truly yours,

  
Conservation Division Agent