

State of Kansas



WM. H. AVERY Governor
WILLIAM L. MITCHELL Chairman
JOHN C. WOELK Commissioner
HARRY G. WILES Commissioner
RAYMOND B. HARVEY Secretary
E. EDWARD JOHNSON Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION
JUN 3 1968
CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Administrator
500 Insurance Building
Wichita 2, Kansas

Dear Sir:

Mr. Dellinger of Knight Casing Pulling has this

date requested permission to plug the following described well:

Mr. Dellinger guarantees payment of the plugging fee.Operator's full Name: Knight Casing Pulling Co.Complete Address: Box 405, Chase, KansasLease Name: Elmer V. Randell Well No. 1Location: C NE SW Sec. 32 Twp. 34 Rge. 21 (E) (W)County Clark Total Depth 5700' Oil Well Gas Well X Input Well SWD Well D & A X Lost Hole Mr. Dellinger was instructed to plug the well as follows:

30" to 30' circulated w/ cement. 20" to 245' circulated w/ cement.

10 3/4" to 605' circulated w/ cement. 4 1/2" to 5622' cemented

Top perforations 5474' Plug bottom w/ sand & 4 sacks cement.Top of cement 5350' Mud 5350' to 600'Rock bridge & 50 sacks cement 600' to 500' Mud 500' to 45'Rock bridge & 15 sacks cement 45' to 0'.

Very truly yours,

Conservation Division Agent