



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION

SEP 20 1965

CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Assistant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

Dear Sir:

Mr. Davis of Sinclair Oil & Gas Co. has this date requested permission to plug the following described well:

Mr. Davis guarantees payment of the plugging fee.

Operator's full Name: Sinclair Oil & Gas Co.

Complete Address: Box 2319 Pampa, Texas

Lease Name: Randall Well No. # 1

Location: C SE NW Sec. 32 Twp. 34 Rge. 21 (E) (W)

County Clark Total Depth 5610 Oil Well X

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Davis was instructed to plug the well as follows:

30"-28' Circulated w/cement. 20"-236' Circulated w/cement.

10 3/4"-638' Circulated w/cement. 5 1/2"-5610' Cemented.

Top perforations 5489'. Plug bottom w/20 Sax. cement top cement 4965'

Mud 4965' to 700' Spotted .50 Sax. cement 700' to 600'

Mud 600' to 50' Plug .25 Sax. cement 50' to 0

Very truly yours,

Hugh Scott
Conservation Division Agent