

15-129-10562-0000

STATE OF KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION
200 Colorado Derby Building
Wichita, Kansas 67202

FORM CP-1
Rev. 2/89

RECEIVED
STATE CORPORATION COMMISSION

WELL PLUGGING APPLICATION FORM
(File One Copy)

MAY 29 1991

CONSERVATION DIVISION
Wichita, Kansas

API NUMBER 11-20-58 (of this well).
(This must be listed; if no API# was issued, please note drilling completion date.)

WELL OWNER/OPERATOR Anadarko Petroleum Corporation OPERATOR'S LICENSE NO. 4549

ADDRESS P.O. Box 351, Liberal, Kansas 67905-0351 PHONE # (316) 624-6253

LEASE (FARM) Interstate Unit* WELL NO. 1 WELL LOCATION 1980' FSL & 1980' FWL COUNTY Morton

SEC. 8 TWP. 34S RGE. 43 (E) or (W) TOTAL DEPTH 4450 PLUG BACK TD 4320

Check One:

OIL WELL GAS WELL D & A SWD or INJ WELL DOCKET NO. E-11,602

SURFACE CASING SIZE 8 5/8 SET AT 1204 CEMENTED WITH 700 SACKS

CASING SIZE 4 1/2 SET AT 4430 CEMENTED WITH 115 SACKS

PERFORATED AT 4353'-86'

CONDITION OF WELL: GOOD POOR CASING LEAK JUNK IN HOLE

PROPOSED METHOD OF PLUGGING TIH w/1-1/4" work string & circ hole w/9.0 ppg mud. Dump

15 sxs common Class "H" cmt from 4320'-4220' (Tbg disp = 4.5 bbls). TOH w/1-1/4" work

string. Pull free point & cut off 4-1/2" csg. Spot 50 sxs cmt @ cut off depth. Spot

(If additional space is needed use back of form.) (over)

IS WELL LOG ATTACHED TO THIS APPLICATION AS REQUIRED? NA IS ACO-1 FILED? Log Filed
(If not explain.)

DATE AND HOUR PLUGGING IS DESIRED TO BEGIN Upon Approval

PLUGGING OF THIS WELL WILL BE DONE IN ACCORDANCE WITH K.S.A. 55-101 et. seq. AND THE RULES AND REGULATIONS OF THE STATE CORPORATION COMMISSION.

NAME OF REPRESENTATIVE AUTHORIZED TO BE IN CHARGE OF PLUGGING OPERATIONS:

Marvin Johnson PHONE # (316) 697-2188

ADDRESS Drawer X, Elkhart, Kansas 67950

PLUGGING CONTRACTOR Sargent's Casing Pulling Service LICENSE NO. 6547

ADDRESS 620 S. Lincoln, Liberal, Kansas 67901 PHONE # (316) 624-7455

PAYMENT OF THE PLUGGING FEE (K.A.R. 82-3-118) WILL BE GUARANTEED BY OPERATOR OR AGENT.

SIGNED: Dawid Kappelo for J.L. Ashton
(Operator or Agent) J. L. Ashton

Div. Production Mgr.

DATE: 5-28-91

50 sxs cmt @ 1204'-1004', spot 40 sxs cmt @ 600'-400', spot 10 sxs cmt @ 50' to 0'.
Cut off csg 3' below ground level & cap well. Restore location.



Kansas Corporation Commission

Joan Finney
Governor

Jim Robinson
Chairman

Keith R. Henley
Commissioner

Rachel C. Lipman
Commissioner

Judith McConnell
Executive Director

Brian J. Moline
General Counsel

NOTICE OF RECEIPT OF WELL PLUGGING APPLICATION

May 29, 1991

Anadarko Petroleum Corporation
P. O. Box 351
Liberal, KS 67905-0351

Interstate Unit 1
1980'FSL-1980'FWL
Sec. 08-34-43W
Morton County

Dear Operator:

This letter is to notify you that the Conservation Division is in receipt of your plugging proposal, form CP-1, for the above-captioned well.

Your CP-1 has been reviewed by the Conservation Division central office for completeness and to verify license numbers. The plugging proposal will now be forwarded to the district office listed below for review of your proposed method of plugging. Please contact the district office for approval of your proposed plugging method at least at five (5) days before plugging the well, pursuant to K.A.R. 82-3-113 (b). Failure to do so is punishable by an administrative penalty of up to \$1000.

It has recently come to my attention that the form CP-1 has been filed by operators other than the owner or operator of the well and without the consent of the owner or operator. The Conservation Division's review of form CP-1, either in the central or district office, does not include an inquiry into well ownership or the filing operator's legal right to plug the well.

This notice in no way constitutes authorization to plug the above-captioned well by persons not having legal rights of ownership or interest in the well. This notice is void after ninety (90) days from the above date.

Sincerely,

David P. Williams
Production Supervisor

District: #1 304 W. McArtor
Dodge City, KS 67801
(316) 225-6760

Conservation Division
William R. Bryson
Director
200 Colorado Derby Bldg.
202 W. 1st Street
Wichita, Kansas 67202-1286
Telephone (316) 263-3238