

15-129-10560-0000

STATE OF KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION
200 Colorado Derby Building
Wichita, Kansas 67202

FORM CP-1
Rev. 6/4/84

WELL PLUGGING APPLICATION FORM
(File One Copy)

API NUMBER 15-129-10560-00-00 (of this well) 8/88
(This must be listed; if no API# was issued, please note drilling completion date.)

LEASE OPERATOR Anadarko Petroleum Corporation OPERATORS LICENSE NO. 4549

ADDRESS P. O. Box 351, Liberal, Kansas 67901 PHONE # (316) 624-6253

LEASE (FARM) *Interstate Unit WELL NO. 5 WELL LOCATION C SE SE COUNTY Morton

SEC. 8 TWP. 34S RGE. 43 or (W) TOTAL DEPTH 4410 PLUG BACK TD 4353

Check One:

OIL WELL _____ GAS WELL _____ D & A _____ SWD or INJ WELL DOCKET NO. 75-605-C

SURFACE CASING SIZE 7" SET AT 1238 CEMENTED WITH 400 SACKS

CASING SIZE 4-1/2 SET AT 4397 CEMENTED WITH 100 SACKS

PERFORATED AT 4309-13

CONDITION OF WELL: GOOD POOR _____ CASING LEAK _____ JUNK IN HOLE _____

OPERATOR'S SUGGESTED METHOD OF PLUGGING THIS WELL Dump 2 sxs of hulls mixed w/gel followed by 50 sxs common cement. Load hole with lease water. Shoot off casing at freepoint. Spot common cement plugs as follows: 30 sxs at casing cut, 40 sxs from 1300-1125, 35 sxs from 650-450 and 10 sxs from 50-0. Spot 9 ppg mud between each plug in the surface casing. Restore location.

(If additional space is needed use back of form)

IS WELL LOG ATTACHED TO THIS APPLICATION AS REQUIRED? _____ IS ACO-1 FILED? Drillers Log Attached
(If not, explain)

DATE AND HOUR PLUGGING IS DESIRED TO BEGIN Upon approval

PLUGGING OF THIS WELL WILL BE DONE IN ACCORDANCE WITH K.S.A. 55-101 et seq AND THE RULES AND REGULATIONS OF THE STATE CORPORATION COMMISSION.

NAME OF COMPANY REPRESENTATIVE AUTHORIZED TO BE IN CHARGE OF PLUGGING OPERATIONS:

Marvin B. Johnson PHONE # (316) 697-2188

ADDRESS P. O. Drawer X, Elkhart, Kansas 67950

PLUGGING CONTRACTOR Sargents Casing Pulling Service LICENSE NO. 6547

ADDRESS 620 S. Lincoln, Liberal, Kansas 67901 PHONE # (316) 624-7455

PAYMENT WILL BE GUARANTEED BY OPERATOR OR AGENT SIGNED: M. L. Pease
(Operator or Agent)

*Formerly Panhandle Eastern Pipe Line Co.
SMITH "B" No.01

M. L. Pease, Division Production Manager
DATE: 10/29/87

RECEIVED
STATE CORPORATION COMMISSION
OCT 23 1987
10-23-87
CONSERVATION DIVISION
Wichita, Kansas 6/88

1



Hike Hayden	Governor
Keith R. Henley	Chairman
Rich Kowalewski	Commissioner
Margalee Wright	Commissioner
Judith A. McConnell	Executive Director

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
 200 Colorado Derby Building
 202 West 1st Street
 WICHITA, KANSAS 67202-1286

THIS NOTICE

JAN 23 '88

October 23, 1987

EXPIRES

WELL PLUGGING NOTICE

Interstate Unit #5 (SWD)
 C SE SE
 Sec. 08-34S-43W
 Morton County

Anadarko Petroleum Corporation
 P. O. Box 351
 Liberal, KS 67901

Gentlemen:

This is your notice to plug the above subject well in accordance with the Rules and Regulations of the State Corporation Commission.

Please contact the district office listed below to review your suggested method of plugging five days prior to plugging the well (KAR-82-3-113).

This notice is void after ninety (90) days from the above date.

Sincerely,

 Shari Feist
 Director
 State Corporation Commission

DISTRICT#1 302 W. McArtor, Dodge City, KS 67801 (316) 225-6760