

15-129-10399-0000

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION  
200 Colorado Derby Building  
Wichita, Kansas 67202

FORM CP-1  
Rev. 6/4/84

WELL PLUGGING APPLICATION FORM  
(File One Copy)

API NUMBER 1/12/59 (of this well) 8/87  
(This must be listed; if no API# was issued, please note drilling completion date.)

LEASE OPERATOR Anadarko Petroleum Corporation OPERATORS LICENSE NO. 4549

ADDRESS P. O. Box 351, Liberal, Kansas 67901 PHONE # (316) 624-6253

LEASE (FARM)\*Interstate Unit WELL NO. 2 WELL LOCATION C SW SW COUNTY Morton

SEC. 8 TWP. 34S RGE. 43 (E) or (W) TOTAL DEPTH 4374 PLUG BACK TD 4100 w/CIBP  
7/26/83

Check One:

OIL WELL  GAS WELL \_\_\_\_\_ D & A \_\_\_\_\_ SWD or INJ WELL \_\_\_\_\_ DOCKET NO. \_\_\_\_\_

SURFACE CASING SIZE 8-5/8 SET AT 1245 CEMENTED WITH 700 SACKS

CASING SIZE 5-1/2 SET AT 4374 CEMENTED WITH 150 SACKS

Squeezed 4319-21 w/150 sxs

PERFORATED AT 4302-10

CONDITION OF WELL: GOOD \_\_\_\_\_ POOR \_\_\_\_\_ CASING LEAK  JUNK IN HOLE \_\_\_\_\_

OPERATOR'S SUGGESTED METHOD OF PLUGGING THIS WELL Using tubing, top CIBP at 4100 with 20 sxs

cement. Load hole with lease water. Shoot off casing at freepoint. Spot 60/40 Poz with 6%

gel cement plugs as follows: 30 sxs at casing cut, 40 sxs from 1345-1145, 35 sxs from 650-480,  
(If additional space is needed use back of form) (over)

IS WELL LOG ATTACHED TO THIS APPLICATION AS REQUIRED? NA IS ACC-1 FILED? Physical  
(If not, explain) Production Reports  
Filed

DATE AND HOUR PLUGGING IS DESIRED TO BEGIN ASAP

PLUGGING OF THIS WELL WILL BE DONE IN ACCORDANCE WITH K.S.A. 55-101 et seq AND THE RULES AND REGULATIONS OF THE STATE CORPORATION COMMISSION.

NAME OF COMPANY REPRESENTATIVE AUTHORIZED TO BE IN CHARGE OF PLUGGING OPERATIONS:

Marvin B. Johnson PHONE # (316) 697-2188

ADDRESS P. O. Drawer X, Elkhart, Kansas 67950

PLUGGING CONTRACTOR Sargents Casing Pulling Service LICENSE NO. 6547 6/87

ADDRESS 620 S. Lincoln, Liberal, Kansas 67901 PHONE # (316) 624-7455

PAYMENT WILL BE GUARANTEED BY OPERATOR OR AGENT David Kapell for M. Pease  
(Operator or Agent)

\*Formerly JM Huber Government "A" No. 6 STATE CORPORATION COMMISSION M. Pease, Division Production Manager

RECEIVED  
MAY 1 8 1987  
DATE: 5/14/87

CONSERVATION DIVISION  
Wichita, Kansas



and 10 sxs from 50-0. Spot 9 ppg mud between each cement plug in the surface casing. Cut off casing below ground level and weld on steel plate. Restore location.

State of Kansas



Mike Hayden Governor  
Keith R. Henley Chairman  
Rich Kowalewski Commissioner  
Margalee Wright Commissioner  
Judith A. McConnell Executive Director

## State Corporation Commission

### CONSERVATION DIVISION

(Oil, Gas and Water)  
200 Colorado Derby Building  
202 West 1st Street  
WICHITA, KANSAS 67202-1286

THIS NOTICE

AUG 18 '87

EXPIRES

May 18, 1987

WELL PLUGGING NOTICE

Interstate Unit #2  
C SW SW  
Sec. 08-34S-43W  
Morton County

Anadarko Petroleum Corporation  
P. O. Box 351  
Liberal, KS 67901

Gentlemen:

This is your notice to plug the above subject well in accordance with the Rules and Regulations of the State Corporation Commission.

This notice is void after ninety (90) days from the above date.

Sincerely,

Shari Feist  
Acting Director  
State Corporation Commission

Please contact the district office to review your suggested method of plugging

DIST. #1 302 West McArtor, Dodge City, KS 67801 (316) 225-6760

five days prior to plugging the well (KAR-82-3-113).