

15-129-10561-0000

STATE OF KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION
200 Colorado Derby Building
Wichita, Kansas 67202

FORM CP-1
Rev. 6/4/84

WELL PLUGGING APPLICATION FORM
(File One Copy)

API NUMBER 15-129-10561-00-00 (of this well) 8/88
(This must be listed; if no API# was issued, please note drilling completion date.)
1/11/58

LEASE OPERATOR Anadarko Petroleum Corporation OPERATORS LICENSE NO. 4549
ADDRESS P. O. Box 351, Liberal, Kansas 67901 PHONE # (316) 624-6253
LEASE (FARM) *Interstate Unit WELL NO. 4 WELL LOCATION C SW SE COUNTY Morton
SEC. 8 TWP. 34S RGE. 43 (E) or (W) TOTAL DEPTH 4404 PLUG BACK TO 4100' w/CIBP

Check One:

OIL WELL GAS WELL _____ D & A _____ SWD or INJ WELL _____ DOCKET NO. _____
SURFACE CASING SIZE 7 SET AT 1256 CEMENTED WITH 450 SACKS
CASING SIZE 4-1/2 SET AT 4404 CEMENTED WITH 75 SACKS
PERFORATED AT 4338-40 for squeeze-200 sxs 4324-34 squeeze-100 sxs

CONDITION OF WELL: GOOD _____ POOR _____ CASING LEAK JUNK IN HOLE _____

OPERATOR'S SUGGESTED METHOD OF PLUGGING THIS WELL CIBP set @ 4100. Dump 20 sxs common cement
on top of CIBP. Load hole with lease water. Shoot off casing at freepoint. Spot common
cement plugs as follows: 30 sxs at casing cut, 40 sxs from 1325-1175, 35 sxs from 650-480
and 10 sxs from 50-0. Spot 9 ppg mud between each plug in the surface casing. Cut off
casing below ground level and cap well. Restore location.
(If additional space is needed use back of form)

IS WELL LOG ATTACHED TO THIS APPLICATION AS REQUIRED? _____ IS ACO-1 FILED? Associated
(If not, explain) State Forms

DATE AND HOUR PLUGGING IS DESIRED TO BEGIN Upon approval

PLUGGING OF THIS WELL WILL BE DONE IN ACCORDANCE WITH K.S.A. 55-101 et seq AND THE RULES AND REGULATIONS OF THE STATE CORPORATION COMMISSION.

NAME OF COMPANY REPRESENTATIVE AUTHORIZED TO BE IN CHARGE OF PLUGGING OPERATIONS RECEIVED
Marvin B. Johnson PHONE # (316) 697-2188
STATE CORPORATION COMMISSION

ADDRESS P. O. Drawer X, Elkhart, Kansas 67950

PLUGGING CONTRACTOR Sargents Casing Pulling Service LICENSE NO. 6547
CONSERVATION DIVISION
6547 Wichita, Kansas 6/88

ADDRESS 620 S. Lincoln, Liberal, Kansas 67901 PHONE # (316) 624-7455

PAYMENT WILL BE GUARANTEED BY OPERATOR OR AGENT SIGNED: M. L. Pease
(Operator or Agent)
M. L. Pease, Division/Production Manager
DATE: 10/20/87

*Formerly Panhandle Eastern Pipe Line Co.
SMITH "B" No. 02





Mike Hayden Governor
Keith R. Henley Chairman
Rich Kowalewski Commissioner
Margalee Wright Commissioner
Judith A. McConnell Executive Director

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
200 Colorado Derby Building
202 West 1st Street
WICHITA, KANSAS 67202-1286

THIS NOTICE

JAN 23 '88

EXPIRES

October 23, 1987
WELL PLUGGING NOTICE

Interstate Unit #4
C SW SE
Sec. 08-34S-43W
Morton County

Anadarko Petroleum Corporation
P. O. Box 351
Liberal, KS 67901

Gentlemen:

This is your notice to plug the above subject well in accordance with the Rules and Regulations of the State Corporation Commission.

Please contact the district office listed below to review your suggested method of plugging five days prior to plugging the well (KAR-82-3-113).

This notice is void after ninety (90) days from the above date.

Sincerely,

Shari Feist
Director
State Corporation Commission

DISTRICT#1 302 W. McArtor, Dodge City, KS 67801 (316) 225-6760