

15-129-30066-0000

STATE OF KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION
200 Colorado Derby Building
Wichita, Kansas 67202

FORM CP-1
Rev. 6/4/84

RECEIVED
STATE CORPORATION COMMISSION

MAR 16 1989

WELL PLUGGING APPLICATION FORM
(File One Copy)

API NUMBER 15-129-30066-00-00
11/3/65 (of this well) 8/89
CONSERVATION DIVISION
Wichita, Kansas

(This must be listed; if no API# was issued, please note drilling completion date.)

LEASE OPERATOR Anadarko Petroleum Corporation OPERATORS LICENSE NO. 4549

ADDRESS P. O. Box 351, Liberal, Kansas 67905-0351 PHONE # (316) 624-6253

LEASE (FARM) Interstate Unit WELL NO. 78 WELL LOCATION SE NW COUNTY Morton

SEC. 32 TWP. 34S RGE. 43 (E) or (W) TOTAL DEPTH 4290' PLUG BACK TO 4100'

Check One:

OIL WELL _____ GAS WELL _____ D & A _____ SWD or INJ WELL X DOCKET NO. 75,605-C

SURFACE CASING SIZE 7" SET AT 1229' CEMENTED WITH 600 SACKS

CASING SIZE 3 1/2" SET AT 4288' CEMENTED WITH 100 SACKS

PERFORATED AT 4190-4222' 2 SPF

CONDITION OF WELL: GOOD _____ POOR X CASING LEAK Possible JUNK IN HOLE _____

OPERATOR'S SUGGESTED METHOD OF PLUGGING THIS WELL Spot 15 sxs common cement on top of

CIBP @ 4100'. Load hole with 9 ppg mud. Cut casing at freepoint and spot 25 sxs common

at cut off. Spot 30 sxs @ 1260' to 1160'. Spot 25 sxs @ 500-400, push wooden wiper plug to 80'

(If additional space is needed use back of form) (over)

IS WELL LOG ATTACHED TO THIS APPLICATION AS REQUIRED? Yes IS ACC-1 FILED? Physical
(If not, explain) (If not, explain) Productivity
Reports Filed

DATE AND HOUR PLUGGING IS DESIRED TO BEGIN Upon Approval

PLUGGING OF THIS WELL WILL BE DONE IN ACCORDANCE WITH K.S.A. 55-101 et seq AND THE RULES AND REGULATIONS OF THE STATE CORPORATION COMMISSION.

NAME OF COMPANY REPRESENTATIVE AUTHORIZED TO BE IN CHARGE OF PLUGGING OPERATIONS:

Marvin B. Johnson PHONE # (316) 697-2188

ADDRESS P. O. Drawer X, Elkhart, Kansas 67950

PLUGGING CONTRACTOR Sargents Casing Pulling Service LICENSE NO. 6547 6/89

ADDRESS 620 S. Lincoln, Liberal, Kansas 67901 PHONE # (316) 624-7455

PAYMENT WILL BE GUARANTEED BY OPERATOR OR AGENT SIGNED: M. L. Pease
(Operator or Agent)

DATE: 3/10/89
M. L. Pease, Division Production Manager

①

and spot 15 sxs @ 80'-3', spot 9 ppg mud between all plugs in surface pipe.



March 10, 1989

Kansas Corporation Commission
200 Colorado Derby Building
202 West First Street
Wichita, KS 67202-1286

Attn: Denise Anderson

Re: Well Plugging Application Form (CP-1)
INTERSTATE UNIT Nos. 71 and 78
Section 32-34S-43W
Morton County, Kansas
INTERSTATE PURDY MORROW UNIT

Dear Ms. Anderson:

Attached for your approval are the KCC Forms No. CP-1
(Well Plugging Application Form) and openhole electrical
logs for the subject wells. The wells are temporarily
abandoned and have no further utility to the unit.

Upon your approval Anadarko will begin plugging operations.
If there are any questions, please contact the above office.

Very truly yours,

A handwritten signature in cursive script that reads "M. L. Pease".

M. L. Pease
Division Production Manager
TAW/vs

Attachments

cc: Well Files w/appropriate attachment
Unit Correspondence File
Per Burchardt

RECEIVED
STATE CORPORATION COMMISSION

MAR 16 1989

CONSERVATION DIVISION
Wichita, Kansas

PAN GEO ATLAS CORP.



Induction-Electrical Log
DEEP INVESTIGATION

FILE NO.	COMPANY ANADARKO PRODUCTION COMPANY		
RECEIVED STATE CORPORATION COMMISSION MAR 16 1965 CONSERVATION Wichita, Kansas	WELL	INTERSTATE UNIT NO. (78)	RES. ENGR.
	FIELD	INTERSTATE	
	COUNTY	MORTON	STATE KANSAS
LOCATION:	2190 E/WL & 2590 S/NL		Other Services
SEC 32	TWP 34S	RGE 43W	A/G MS

Permanent Datum	GROUND LEVEL	Elev. 3541.0	Elevations: KB 3550.0
Log Measured from	GROUND LEVEL	0 Ft. Above Permanent Datum	DF 3548.5
Drilling Measured from	GROUND LEVEL		GL 3541.0

Date	11-2-65				
Run No.	ONE				
Depth—Driller	4290				
Depth—Logger	4291				
Bottom Logged Interval	4285				
Top Logged Interval	1230				
Casing—Driller	7" @ 1230	@	@	@	@
Casing—Logger	1230				
Bit Size	6 1/4"				
Type Fluid in Hole	CHEMICAL 5% OIL				
Density and Viscosity	9 48				
pH and Fluid Loss	9 8.4 cc	cc	cc	cc	cc
Source of Sample	CIRCULATED				
Rm @ Meas. Temp.	.9 @ 82 °F	@ °F	@ °F	@ °F	@ °F
Rmf @ Meas. Temp.	.67 @ 66 °F	@ °F	@ °F	@ °F	@ °F
Rmc @ Meas. Temp.	2.1 @ 66 °F	@ °F	@ °F	@ °F	@ °F
Source of Rmf and Rmc	MP MP				
Rm @ BHT	.69 @ 113 °F	@ °F	@ °F	@ °F	@ °F
Time Since Circ.	2 HOURS				
Max. Rec. Temp. Deg. F.	113 °F	°F	°F	°F	°F
Equip. No. and Location	EL-43 LIBERAL				
Recorded By	HUBBARD <i>Ray</i>				
Witnessed By	MR. POSEY				

State of Kansas



Kansas Corporation Commission

MIKE HAYDEN
KEITH R. HENLEY
RICH KOWALEWSKI
MARGALEE WRIGHT
JUDITH McCONNELL
FRANK A. CARO, JR.

GOVERNOR
CHAIRMAN
COMMISSIONER
COMMISSIONER
EXECUTIVE DIRECTOR
GENERAL COUNSEL

CONSERVATION DIVISION
SHARI M. FEIST, DIRECTOR
200 Colorado Derby Bldg.
202 W. 1st Street
Wichita, KS 67202-1286
(316) 263-3238

THIS NOTICE

JUN 17 1989

EXPIRES

March 17, 1989

NOTICE OF RECEIPT OF
WELL PLUGGING APPLICATION

Anadarko Petroleum Corporation
P. O. Box 351
Liberal, KS 67905-0351

Interstate Unit #78 (SWD)
SE NW
Sec. 32-34S-43W
Morton County

Gentlemen:

This letter is to notify you that the Conservation Division is in receipt of your plugging proposal, form CP-1, for the above-captioned well.

Your CP-1 has been reviewed by the Conservation Division central office for completeness and to verify license numbers. The plugging proposal will now be forwarded to the district office listed below for review of your proposed method of plugging. Please contact the district office to review your proposed plugging method at least five (5) days before plugging the well.

It has recently come to my attention that the form CP-1 has been filed by operators other than the owner or operator of the well and without the consent of the owner or operator. The Conservation Division's review of form CP-1, either in the central or district office, does not include an inquiry into well ownership or the filing operator's legal right to plug the well. The CP-1 is simply reviewed to determine compliance with plugging rules and regulations.

This notice in no way constitutes authorization to plug the above-captioned well by persons not having legal rights of ownership or interest in the well. This notice is void after ninety (90) days from the above date.

Sincerely,

Shari Feist Albrecht

Shari Feist Albrecht
Director

District: #1 304 W. McArtor
Dodge City, KS 67801
(316) 225-6760