

STATE OF KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION
200 Colorado Derby Building
Wichita, Kansas 67202

FORM CP-1
Rev.03/92

WELL PLUGGING APPLICATION FORM
(PLEASE TYPE FORM and File ONE Copy)

API # 15-129-21,220-⁰⁰⁰⁰ (Identifier number of this well). This must be listed for wells drilled since 1967; if no API# was issued, indicate spud or completion date.

WELL OPERATOR ANADARKO PETROLEUM CORPORATION KCC LICENSE # 4549
(owner/company name) (operator's)

ADDRESS P. O. BOX 351 CITY LIBERAL

STATE KANSAS ZIP CODE 67905-0351 CONTACT PHONE # (316) 624-6253

LEASE LINSCOTT "B" WELL# 9 SEC. 32 T. 34S R. 43 (XXXX West)

NE - NE - SE - SW SPOT LOCATION/QQQQ COUNTY MORTON

1250 FEET (in exact footage) FROM S/X (circle one) LINE OF SECTION (NOT Lease Line)

2480 FEET (in exact footage) FROM X/W (circle one) LINE OF SECTION (NOT Lease Line)

Check One: OIL WELL GAS WELL X D&A SWD/ENHR WELL DOCKET#

CONDUCTOR CASING SIZE SET AT CEMENTED WITH SACKS

SURFACE CASING SIZE 8 5/8 SET AT 679 CEMENTED WITH 425 SACKS

PRODUCTION CASING SIZE 5 1/2 SET AT 2976 CEMENTED WITH 355 SACKS

LIST (ALL) PERFORATIONS and BRIDGEPLUG SETS: 2882-90, 2840-50, 2815-21, 2785-2804,
2745-48, 2730-32, 2693-95, CIBP @ 2875

ELEVATION 3532' T.D. 3000' PBDT 2875' ANHYDRITE DEPTH
(G.L./K.B.) (Stone Corral Formation)

CONDITION OF WELL: GOOD X POOR CASING LEAK JUNK IN HOLE

PROPOSED METHOD OF PLUGGING MIRU CSG PULLERS. MIX AND PUMP 2 SXS HULLS AND 30 SXS CMT PLUG FROM 2643-2850'. DISPLACE W/63 BBLs 9 PPG MUD. PULL ON 5-1/2" CSG, LOCATE FREE POINT AND SHOOT OFF. SPOT 35 SXS CMT PLUG AT CUT OFF POINT. PULL 5-1/2" CSG TO 729'. SPOT 35 SXS CMT PLUG FROM 729-629'. TOH W/5-1/2" CSG AND SPOT 15 SXS CMT PLUG FROM 53-3'. CUT OFF 8-5/8" CSG 3' BELOW GROUND LEVEL AND CAP. INSCRIBE WELL NAME AND NUMBER, LEGAL DESCRIPTION AND PLUGGING DATE ON CAP. RDMO CSG PULLERS AND RESTORE LOCATION.

(If additional space is needed attach separate page)

IS WELL LOG ATTACHED TO THIS APPLICATION AS REQUIRED? IS ACO-1 FILED? YES

If not explain why?

PLUGGING OF THIS WELL WILL BE DONE IN ACCORDANCE WITH K.S.A. 55-101 et. seq. AND THE RULES AND REGULATIONS OF THE STATE CORPORATION COMMISSION.

LIST NAME OF COMPANY REPRESENTATIVE AUTHORIZED TO BE IN CHARGE OF PLUGGING OPERATIONS:

MARVIN JOHNSON PHONE# (316) 697-2188

ADDRESS P.O. DRAWER X City/State ELKHART, KANSAS 67951

PLUGGING CONTRACTOR SARGENT & HORTON PLUGGING, INC. KCC LICENSE # 31151
(company name) (contractor's)

ADDRESS RT. 1, BOX 49BA, TYRONE, OK 73951-9731 PHONE # (405) 854-6515

PROPOSED DATE AND HOUR OF PLUGGING (If Known?) UPON APPROVAL

OCT 12 1994

PAYMENT OF THE PLUGGING FEE (K.A.R. 82-3-118) WILL BE GUARANTEED BY OPERATOR OR AGENT

DATE: 10-9-94 AUTHORIZED OPERATOR/AGENT: J. L. Ashton
J. L. ASHTON (signature)

STATE CORPORATION COMMISSION
WICHITA, KANSAS



Kansas Corporation Commission

Joan Finney, Governor Susan M. Seltsam, Chair F.S. Jack Alexander, Commissioner Rachel C. Lipman, Commissioner
Judith McConnell, Executive Director Brian Moline, General Counsel

NOTICE OF RECEIPT OF WELL PLUGGING APPLICATION (CP-1)

October 14, 1994

Anadarko Petroleum Corporation
P O Box 351
Liberal KS 67905-0351

Linscott "B" #9
API 15-129-21,220
1250 FSL 2480 FWL
Sec. 32-34S-43W
Morton County

Dear Marvin Johnson,

This letter is to notify you that the Conservation Division is in receipt of your plugging proposal, form CP-1, for the above-captioned well.

Your CP-1 has been reviewed by the Conservation Division central office for completeness and to verify license numbers. The plugging proposal will now be forwarded to the district office listed below for review of your proposed method of plugging.

Please contact the district office for approval of your proposed plugging method at least at five (5) days before plugging the well, pursuant to K.A.R. 82-3-113 (b). If a workover pit will be used during the plugging of the well it must be permitted. A CDP-1 form must be filed and approved prior to the use of the pit.

The Conservation Division's review of form CP-1, either in the central or district office, does not include an inquiry into well ownership or the filing operator's legal right to plug the well.

This notice in no way constitutes authorization to plug the above-captioned well by persons not having legal rights of ownership or interest in the well. This notice is void after ninety (90) days from the above date.

Sincerely,


David P. Williams
Production Supervisor

District: #1
304 W. McArtor
Dodge City KS 67801
(316) 225-6760