

15-129-10441-0000

STATE OF KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION
200 Colorado Derby Building
Wichita, Kansas 67202

FORM CP-1
Rev. 6/4/84

WELL PLUGGING APPLICATION FORM
(File One Copy)

API NUMBER 15-129-10441-00-00 (of this well) 8/87
3/9/56
(This must be listed; if no API# was issued, please note drilling completion date.)

LEASE OPERATOR Anadarko Petroleum Corporation OPERATORS LICENSE NO. 4549

ADDRESS P. O. Box 351, Liberal, Kansas 67901 PHONE # (316) 624-6253

LEASE (FARM) *Interstate Unit WELL NO. 76 WELL LOCATION C SE NE COUNTY Morton

SEC. 31 TWP. 34S RGE. 43 or (W) TOTAL DEPTH 4283 PLUG BACK TD 4100 w/CIBP
8/1/83

Check One:

OIL WELL GAS WELL _____ D & A _____ SWD or INJ WELL _____ DOCKET NO. _____

SURFACE CASING SIZE 8-5/8 SET AT 1218 CEMENTED WITH 600 SACKS

CASING SIZE 5-1/2 SET AT 4282 CEMENTED WITH 250 SACKS

PERFORATED AT 4202-4211

CONDITION OF WELL: GOOD _____ POOR _____ CASING LEAK JUNK IN HOLE _____

OPERATOR'S SUGGESTED METHOD OF PLUGGING THIS WELL Cap CIBP with 20 sxs cement using tubing.

Load hole with lease water. Shoot off casing at freepoint. Set 60/40 Poz with 6% gel cement
plugs as follows: 30 sxs @ casing cut; 40 sxs from 1300-1100'; 35 sxs from 650-480'; 10 sxs
(If additional space is needed use back of form) (over

IS WELL LOG ATTACHED TO THIS APPLICATION AS REQUIRED? NA IS ACO-1 FILED? No record
(If not, explain) of any state forms sent

DATE AND HOUR PLUGGING IS DESIRED TO BEGIN ASAP

PLUGGING OF THIS WELL WILL BE DONE IN ACCORDANCE WITH K.S.A. 55-101 et seq AND THE RULES AND REGULATIONS OF THE STATE CORPORATION COMMISSION.

NAME OF COMPANY REPRESENTATIVE AUTHORIZED TO BE IN CHARGE OF PLUGGING OPERATIONS:

Marvin B. Johnson PHONE # (316) 697-2188

ADDRESS P. O. Drawer X, Elkhart, Kansas 67950

PLUGGING CONTRACTOR Sargents Casing Pulling Service LICENSE NO. 6547 6/87

ADDRESS 620 S. Lincoln, Liberal, Kansas 67901 PHONE # (316) 624-7455

PAYMENT WILL BE GUARANTEED BY OPERATOR OR AGENT SIGNED: M. L. Pease
(Operator or Agent)

*Formerly Musgrove Petroleum Corporation BROWN #3 M. L. Pease, Division Production Engineer

DATE: August 28, 1986

9-2-86
SEP 2 1986



from 50'-0'. Cut off casing below ground level. Weld on steel plate. Spot 9 ppg mud between all cement plugs in the surface casing. Restore location.

State of Kansas



JOHN CARLIN
MICHAEL LENNEN
MARGALEE WRIGHT
KEITH R. HENLEY
JUDITH A. McCONNELL
BRIAN J. MOLINE

Governor
Chairman
Commissioner
Commissioner
Executive Secretary
General Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
200 Colorado Derby Building
202 West 1st Street
WICHITA, KANSAS 67202-1286

THIS NOTICE

DEC 2 '86

EXPIRES

September 2, 1986

WELL PLUGGING NOTICE

Interstate Unit #76
C SE NE
Sec. 31-34S-43W
Morton County

Anadarko Production Corporation
P. O. Box 351
Liberal, KS 67901

Gentlemen:

This is your notice to plug the above subject well in accordance with the Rules and Regulations of the State Corporation Commission.

This notice is void after ninety (90) days from the above date.

Sincerely,

Jack McCord, Director

Please contact the district office to review your suggested method of plugging

DIST. #1 302 West McArtor Dodge City, KS 67801 316-225-6760

five days prior to plugging the well (KAR-82-3-113).