

15-129-10440-0000

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION  
200 Colorado Derby Building  
Wichita, Kansas 67202

FORM CP-1  
Rev. 6/4/84

WELL PLUGGING APPLICATION FORM  
(File One Copy)

API NUMBER 15-129-10440-00-00 (of this well) 8/87  
(This must be listed; if no API# was issued, please note drilling completion date.)  
3/9/56

LEASE OPERATOR Anadarko Petroleum Corporation OPERATORS LICENSE NO. 4549

ADDRESS P. O. Box 351, Liberal, Kansas 67901 PHONE # (316) 624-6253

LEASE (FARM)\*Interstate Unit WELL NO. 73 WELL LOCATION C NE COUNTY Morton

SEC. 31 TWP. 34S RGE. 43  OIL  (W) TOTAL DEPTH 4551 PLUG BACK TD 4100 w/CIBP  
7/29/83

Check One:

OIL WELL  GAS WELL \_\_\_\_\_ D & A \_\_\_\_\_ SWD or INJ WELL \_\_\_\_\_ DOCKET NO. \_\_\_\_\_

SURFACE CASING SIZE 8-5/8 SET AT 1240 CEMENTED WITH 600 SACKS

CASING SIZE 5-1/2 SET AT 4527 CEMENTED WITH 250 SACKS

PERFORATED AT 4228-4237

CONDITION OF WELL: GOOD \_\_\_\_\_ POOR \_\_\_\_\_ CASING LEAK  JUNK IN HOLE \_\_\_\_\_

OPERATOR'S SUGGESTED METHOD OF PLUGGING THIS WELL Top CIBP @ 4100' with 20 sxs cement using

tubing. Load hole with lease water. Shoot off casing at freepoint. Spot 60/40 Poz with 6%

gel cement plugs as follows: 30 sxs @ casing cut; 40 sxs from 1300-1100'; 35 sxs from 650-480';  
(If additional space is needed use back of form) (over)

IS WELL LOG ATTACHED TO THIS APPLICATION AS REQUIRED? NA IS ACO-1 FILED? No record of  
(If not, explain) any State Forms filed.

DATE AND HOUR PLUGGING IS DESIRED TO BEGIN ASAP

PLUGGING OF THIS WELL WILL BE DONE IN ACCORDANCE WITH K.S.A. 55-101 et seq AND THE RULES AND REGULATIONS OF THE STATE CORPORATION COMMISSION.

NAME OF COMPANY REPRESENTATIVE AUTHORIZED TO BE IN CHARGE OF PLUGGING OPERATIONS:

Marvin B. Johnson PHONE # (316) 697-2188

ADDRESS P. O. Drawer X, Elkhart, Kansas 67950

PLUGGING CONTRACTOR Sargents Casing Pulling Service LICENSE NO. 6547 6/87

ADDRESS 620 S. Lincoln, Liberal, Kansas 67901 PHONE # (316) 624-7455

PAYMENT WILL BE GUARANTEED BY OPERATOR OR AGENT SIGNED: M. L. Pease  
(Operator or Agent)

\*Formerly Musgrove Petroleum Corporation BROWN #2 M. L. Pease, Division Production Engineer

DATE: August 28, 1986

①

9-2-86  
SEP 2 1986

10 sxs from 50-0'. Cut off casing below ground level. Weld on steel plate. Spot 9 ppg mud between all cement plugs in the surface casing. Restore location.

State of Kansas



JOHN CARLIN  
MICHAEL LENNEN  
MARGALEE WRIGHT  
KEITH R. HENLEY  
JUDITH A. MCCONNELL  
BRIAN J. MOLINE

Governor  
Chairman  
Commissioner  
Commissioner  
Executive Secretary  
General Counsel

## State Corporation Commission

### CONSERVATION DIVISION

(Oil, Gas and Water)  
200 Colorado Derby Building  
202 West 1st Street  
WICHITA, KANSAS 67202-1286

THIS NOTICE

DEC 2 '86

EXPIRES

September 2, 1986

#### WELL PLUGGING NOTICE

Interstate Unit #73  
C NE  
Sec. 31-34S-43W  
Morton County

Anadarko Production Corporation  
P. O. Box 351  
Liberal, KS 67901

Gentlemen:

This is your notice to plug the above subject well in accordance with the Rules and Regulations of the State Corporation Commission.

This notice is void after ninety (90) days from the above date.

Sincerely,

Jack McCord, Director

Please contact the district office to review your suggested method of plugging  
DIST. #1 302 West McArtor Dodge City, KS 67801 316-225-6760  
five days prior to plugging the well (KAR-82-3-113).