

RECEIVED  
OCT 08 2003  
KCC WICHITA

KANSAS CORPORATION COMMISSION  
OIL & GAS CONSERVATION DIVISION  
WELL PLUGGING APPLICATION  
Please TYPE Form and File ONE Copy

Form CP-1  
September 2003  
This Form must be Typed  
Form must be Signed  
All blanks must be Filled

API # 15 - 119-30000-00-01 (Identifier Number of this well). This must be listed for wells drilled since 1967; if no API # was issued, indicate original spud or completion date \_\_\_\_\_

Well Operator: Great Plains Petroleum, Inc. KCC License #: 30163 7/04  
(Owner / Company Name) (Operator's)

Address: 221 Circle Drive City: Wichita

State: Kansas Zip Code: 67218 Contact Phone: (316) 685 - 8800

Lease: Thonoff "E" Well #: 1 Sec. 4 Twp. 35 S. R. 27  East  West

SW Spot Location / QQQQ County: Meade

1420 Feet (in exact footage) From  North /  South (from nearest outside section corner) Line of Section (Not Lease Line)

1250 Feet (in exact footage) From  East /  West (from nearest outside section corner) Line of Section (Not Lease Line)

Check One:  Oil Well  Gas Well  D&A  Cathodic  Water Supply Well  
 SWD Docket # \_\_\_\_\_  ENHR Docket # \_\_\_\_\_  Other: \_\_\_\_\_

Conductor Casing Size: none Set at: \_\_\_\_\_ Cemented with: \_\_\_\_\_ Sacks

Surface Casing Size: 8-5/8 Set at: 1251 Cemented with: 670 Sacks

Production Casing Size: 5-1/2 Set at: 6862 Cemented with: 150 Sacks

List (ALL) Perforations and Bridgeplug Sets: Perfs @ 6806-6811, 3230-3236, 3199-3201.

CIBP @ 3310. Cement from 3310 to 2800.

Elevation: 2341 ( G.L. /  K.B.) T.D.: 6865 PBTD: 2800 Anhydrite Depth: no log, est. 1210'  
(Stone Corral Formation)

Condition of Well:  Good  Poor  Casing Leak  Junk in Hole

Proposed Method of Plugging (attach a separate page if additional space is needed): Cut and pull 5-1/2 casing below 1230'. Set wooden plug at 1230' and spot 50 sx of cement. Fill 8-5/8 casing with mud. Spot 25 sx of cement from 200' to 115'. Fill 8-5/8 casing with mud, spot 10 sx of cement from 45' to 0'.

Is Well Log attached to this application as required?  Yes  No Is ACO-1 filed?  Yes  No

If not explain why? Re-entered this old plugged well on September 30, 2003. All top plugs were in place, and we pressure tested 8-5/8 casing to 600#. Encountered parted casing @ 1970' and could not drill past. Will file ACO-1 when job done.

Plugging of this Well will be done in accordance with K.S.A. 55-101 et. seq. and the Rules and Regulations of the State Corporation Commission.

List Name of Company Representative authorized to be in charge of plugging operations: Rod A. Phares

Great Plains Petroleum, Inc. Phone: (316) 685 - 8800

Address: 221 Circle Drive City / State: Wichita, KS

Plugging Contractor: Best Well Service KCC License #: 32564

Address: Liberal, KS Phone: (316) 629 - 1766

Proposed Date and Hour of Plugging (if known?): 12:00 PM, October 7, 2003

Payment of the Plugging Fee (K.A.R. 82-3-118) will be guaranteed by Operator or Agent

Date: 10/6/03 Authorized Operator / Agent: Rod A. Phares  
(Signature)

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

12/03



CORPORATION COMMISSION

Kathleen Sebelius, Governor    Brian J. Moline, Chair    John Wine, Commissioner    Robert E. Krehbiel, Commissioner

**NOTICE OF RECEIPT OF WELL PLUGGING APPLICATION (CP-1)**

Great Plains Petroleum, Inc.  
221 Circle Drive  
Wichita, KS 67218

October 08, 2003

Re: THONOFF E #1  
API 15-119-30000-00-01  
SESENW 4-35S-27W, 1420 FSL 1250 FWL  
MEADE COUNTY, KANSAS

Dear Operator:

This letter is to notify you that the Conservation Division is in receipt of your plugging proposal, form CP-1, for the above-captioned well.

Your CP-1 has been reviewed by the Conservation Division central office for completeness and to verify license numbers. The plugging proposal will now be forwarded to the district office listed below for review of your proposed method of plugging.

**Please contact the district office for approval of your proposed plugging method at least five (5) days before plugging the well, pursuant to K.A.R. 82-3-113 (b). If a workover pit will be used during the plugging of the well it must be permitted. A CDP-1 form must be filed and approved prior to the use of the pit.**

The Conservation Division's review of form CP-1, either in the central or district office, does not include an inquiry into well ownership or the filing operator's legal right to plug the well.

**This notice in no way constitutes authorization to plug the above-captioned well by persons not having legal rights of ownership or interest in the well. This notice is void after ninety (90) days from the above date.**

District: #1  
210 E Frontview, Suite A  
Dodge City, KS 67801  
(316) 225-8888

Sincerely  


David P. Williams  
Production Supervisor