

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-119-20825-00-00  
Spot: CSE Sec/Twnshp/Rge: 5-35S-27W  
1320 feet from S Section Line, 1320 feet from E Section Line  
Lease/Unit Name: ALFRED Well Number: 1  
County: MEADE Total Vertical Depth: 3400 feet

Operator License No.: 32972  
Op Name: THE SOUTH FORTY, INC.  
Address: PO BOX 446  
LAVERNE, OK 73848

Conductor Pipe: Size 13.375 feet: 80  
Surface Casing: Size 8.625 feet: 1202 WITH 475 SX CMT 8/10.50  
Production: Size 4.5 feet: 3378  
Liner: Size feet:

Well Type: GAS UIC Docket No: Date/Time to Plug: 05/16/2002 9:30 AM  
Plug Co. License No.: 32833 Plug Co. Name: SARGENT LILLARD CASING PULLING, INC.  
Proposal Rcvd. from: KIRBY LILLARD Company: SARGENT LILLARD CASING PULL Phone: (580) 254-1881

Proposed Plugging Method: PUMP 20 SX CMT & 200# HULLS TO 3100'. 1ST PLUG AT 1220' WITH 50 SX CMT. 2ND PLUG AT 500' WITH 25 SX CMT. 3RD PLUG AT 0-40' WITH 10 SX CMT.

Plugging Proposal Received By: STEVE MIDDLETON WitnessType: Plugging Operations 100% Witnessed (Complete)  
Date/Time Plugging Completed: 05/16/2002 11:30 AM KCC Agent: STEVE MIDDLETON

Actual Plugging Report:

PERFS AT 3226-3230'. PUMP 20 SX CMT & 100# HULLS OVER PERFS. 1ST PLUG LOAD HOLE WITH MUD. PULL TO 1220' & PUMP 50 SX CMT. 2ND PLUG PULL TO 500' & SPOT 30 SX CMT. 3RD PLUG PULL TO 40' & SPOT 10 SX CMT. STAYED FULL.

RECEIVED

MAY 20 2002  
S-20-02  
KCC WICHITA

Remarks: USED COMMON CEMENT BY SARGET & LILLARD. RECOVERED 2650' OF 4 1/2" CASING.

Plugged through: CSG

District: 01

Signed

  
(TECHNICIAN)

INVOICED MAY 16 2002

DATE 5-21-02

INV. NO. 2002061831 

