

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-119-30000-00-01
Spot: SESENW Sec/Twnshp/Rge: 4-35S-27W
1420 feet from S Section Line, 1250 feet from W Section Line
Lease/Unit Name: THONOFF E Well Number: 1
County: MEADE Total Vertical Depth: 2210 feet

Operator License No.: 30163
Op Name: GREAT PLAINS PETROLEUM, INC.
Address: 221 CIRCLE DRIVE
WICHITA, KS 67218

Production Casing Size: 5.5 feet: 6862 WITH 150 SX CMT
Surface Casing Size: 8.625 feet: 1251 WITH 670 SX CMT

71⁸³

Well Type: DH UIC Docket No: _____ Date/Time to Plug: 10/07/2003 1:00 PM
Plug Co. License No.: 32564 Plug Co. Name: TONY L. BRUCE DBA BEST WELL SERVICE
Proposal Rcvd. from: ROD A. PHARES Company: GRAT PLAINS Phone: (316) 685-8800

Proposed Plugging Method: STUB PLUG AT 1410' WITH 20 SX CMT. PLUG AT 1275' WITH 50 SX CMT. PLUG AT 200' WITH 20 SX CMT. PLUG AT 40' WITH 10 SX CMT.

Plugging Proposal Received By: STEVE MIDDLETON WitnessType: Plugging Operations 100% Witnessed (Complete)
Date/Time Plugging Completed: 10/07/2003 3:30 PM KCC Agent: STEVE MIDDLETON

Actual Plugging Report:
WASHED DOWN WELL TO 2210'. COULD NOT GET DEEPER. ORIGINAL TD 6865'. STUB PLUG AT 1410' WITH 20 SX CMT. 1ST PLUG PLUG LOAD HOLE WITH MUD. PULL CASING TO 1280' & SPOT 50 SX CMT. 2ND PLUG PULL TO 350' & SPOT 25 SX CMT. 3RD PLUG PULL TO 30' & SPOT 10 SX CMT. STAYED FULL THROUGH OUT JOB.

RECEIVED
OCT 14 2003
KCC WICHITA

Remarks: USED 60/40 POZMIX 6% GEL BY ALLIED. RECOVERED 1440' OF 5 1/2" CASING.

Plugged through: CSG

District: 01

RECEIVED
OCT - 9 2003
KCC Dodge City

Signed _____
(TECHNICIAN)

INVOICED
DATE 10-14-03
NO. 2004060617

Form CP-2/3
SA