

To: 1 100042
STATE CORPORATION COMMISSION
Wichita State Office Bldg. - PLUGGING SECTION
130 S. Market, Room 2078
Wichita, KS 67202

API NUMBER 15-119-20,012 - 0000

S/2 SW, SEC. 3, T 35 S, R 27 WXX
500 feet from S section line
3960 feet from E section line

4-30

TECHNICIAN'S PLUGGING REPORT
Operator License / 4247
Operator: Dolomite Resources
Name & Address: 105 S. Broadway, Ste. 740
Wichita, KS 67202

Lease Name Merkle Well # 1
County Meade 205.30
Well Total Depth 6317 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 1256

Abandoned Oil Well _____ Gas Well Input Well _____ SMO Well _____ O&A _____
Other well as hereinafter indicated _____

Plugging Contractor Jerry Dunkin, Inc. License Number 8733
Address P.O. Box 389, Enid, OK 73702

Company to plug at: Hour: 1 p.m. Day: 30 Month: 4 Year: 19 96

Plugging proposal received from Ray Bennett
(company name) Jerry Dunkin, Inc. (phone) 405-237-6152

were: 4 1/2" at 6266' w/75 sx cement, PBSD 3140', Perfs at 6126-80'
1st plug at 2850' with 25 sx cement and 200 lbs. hulls,
2nd plug spot 50 sx cement at 1286',
3rd plug spot 50 sx cement at 600',
4th plug at 40-0' with 10 sx cement.

Plugging Proposal Received by Gary Winters (TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 3 p.m. Day: 30 Month: 4 Year: 19 96

ACTUAL PLUGGING REPORT 1st plug at 2850' with 25 sx cement and 200 lbs. hulls,
2nd plug spotted 50 sx cement at 1286',
3rd plug spotted 50 sx cement at 600',
4th plug at 40-0' with 10 sx cement.

RECEIVED
KANSAS CORPORATION COMMISSION

MAY 14 1996

Remarks: Used Class A common cement by Jerry Dunkin. Recovered 2092' of 4 1/2" casing.
(If additional description is necessary, use BACK of this form.)

INVOLVED

DATE 5-15-96
INV. NO. 45599

Signed Gary Winters (TECHNICIAN)