

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-119-20784-00-00  
Spot: CNENE Sec/Twnshp/Rge: 1-35S-27W  
4620 feet from S Section Line, 660 feet from E Section Line  
Lease/Unit Name: BERNNIE Well Number: 1  
County: MEADE Total Vertical Depth: 6500 feet

Operator License No.: 8060  
Op Name: ZINKE & TRUMBO, INC.  
Address: 1202 E. 33RD ST., STE 100  
TULSA, OK 74105

Conductor Pipe: Size 20 feet: 80 \$211.25  
Surface Casing: Size 8.625 feet: 576 WITH 225 SX CMT  
Production: Size 4.5 feet: 6500 WITH 190 SX CMT  
Liner: Size \_\_\_\_\_ feet: \_\_\_\_\_

Well Type: GAS UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 07/16/2002 12:30 PM  
Plug Co. License No.: 8733 Plug Co. Name: DUNKIN, JERRY, INC.  
Proposal Rcvd. from: DON BROWN Company: CROWN CONSULTING Phone: (620) 624-0156

Proposed Plugging Method: SET CIBP @ 6300', DUMP 2 SX CMT. ON PLUG, 50 SX @ 12000', 50 SX @ 600', 10 SX @ 40', PER STEVE DURRANT WITH KCC 04-26-2002.

Plugging Proposal Received By: STEVE DURRANT Witness Type: Plugging Operations 100% Witnessed (Complete)  
Date/Time Plugging Completed: 07/16/2002 3:10 PM KCC Agent: STEVE MIDDLETON

Actual Plugging Report:

PBTD 6427'. PERFS AT 6345-6358'. CIBP @ 6300' WITH 2 SX CMT. 1ST PLUG LOAD HOLE WITH MUD. 2ND PLUG PULL TO 1200' AND SPOT 50 SX CMT. 3RD PLUG PULL TO 600' AND SPOT 50 SX CMT. 4TH PLUG PULL TO 40'. CIRCULATE 10 SX CMT TO SURFACE. STAYED FULL.

RECEIVED  
JUL 19 2002  
7-19-02  
KCC WICHITA

Remarks: USED CLASS A CEMENT BY DUNCAN WELL SERVICE. RECOVERED 2746' OF 4 1/2" CASING.

Plugged through: CSG

District: 01

Signed \_\_\_\_\_

(TECHNICIAN)

INVOICED

JUL 16 2002

DATE 7-19-02

INV. NO. 2003060064

Form 2223