

To: 1051623 2-8
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 119-20,664 - 0000
NW NW NW, SEC. 5, T 35 S, R 26 W/E
4950 feet from S section line
4850 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 8060
Operator: Zinke & Trumbo, Ltd.
Name & Address: 1202 E. 33rd, Ste. 100
Tulsa, OK 74105

Lease Name Ediger Well # 1-5
County Meade 204.75
Well Total Depth 6300 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 1517

Abandoned Oil Well _____ Gas Well Input Well _____ SMD Well _____ D&A _____
Other well as hereinafter indicated _____

Plugging Contractor Sargent's Casing Pulling License Number 6547
Address 620 S. Lincoln, Liberal, KS 67901

Company to plug at: Hour: 10 a.m. Day: 8 Month: 2 Year: 19 93

Plugging proposal received from Kirby Lillard
(company name) Sargent's Casing Pulling (phone) 316-624-7455

Work: 4 1/2" at 6296' w/300 sx cement, PBSD 6256', Perfs at 5910-36'
1st plug pump 2 sx hulls and 20 sx cement to 5800',
2nd plug pump 50 sx cement at 1550',
3rd plug pump 40 sx cement at 600',
4th plug pump 10 sx cement at 40'.

Plugging Proposal Received by Richard Lacey
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 5 p.m. Day: 8 Month: 2 Year: 19 93

ACTUAL PLUGGING REPORT 1st plug pumped 2 sx hulls and 20 sx cement to 5800',
2nd plug pumped 50 sx cement at 1550',
3rd plug pumped 40 sx cement at 600',
4th plug pumped 10 sx cement at 40'.

Remarks: Used common cement by Sargent's. Recovered 2845' of 4 1/2" casing.
(If additional description is necessary, use BACK of this form.)
RECEIVED STATE CORPORATION COMMISSION FEB 10 1993 CONSERVATION DIVISION Wichita, Kansas

I (did / ~~did not~~) observe this plugging.

INVOICED
DATE 2-17-93
INV. NO. 37371
2-8

Signed Richard W. Lacey
(TECHNICIAN)